

SUMMARY OF QUANTITIES

Work Order No.	County/Municipality	Map No.	Route No./Name	To/From Description	Typ Sect No	Length	Final Width	Inc Stone Base	Mill Asph Pvmnt 1 1/2"	Mill Asph Pvmnt 0" to 1 1/2"	Mill Asph Pvmnt 0" to Var. Dpth	ACSC Type S9.5B	ACSC Type S9.5C	PG 64-22 Plant Mix	PG 70-22 Plant Mix	Patch Exist Pvmnt	Adjust CB	Adjust MH	Adjust MB / VB
						MI	FT	TONS	SY	SY	SY	TONS	TONS	TONS	TONS	TONS	EA	EA	EA
9CR.10801.3	Rowan	1	NC 801	Pvmt Jt at Iredell Co Line to Pvmt Jt at SR 1753 (Centenary Church Rd)	3	2.312	24	23		111			3,024		181	20			
		2	NC 801	Pvmt Jt at NC 801 at SR 1526 (Sherrills Ford Rd) to SR 1743 (Bear Poplar Rd)	3	2.132	24	21					2,816		169	20			
TOTAL FOR WORK ORDER NO. 9CR.10801.3						4.444		44	0	111	0	0	5,840	0	350	40	0	0	0
9CR.20801.3	Rowan	3	SR 2538 Peeler Rd	US 29 to Pvmt Jt after Bridge #281, Before SR 2661 (Waddell Dr)	3	0.579	27	6	221	600			851		51	20			
		4	SR 1910 Old Mocksville Rd	SR 1915 (East Ridge Rd) to Pvmt Jt at US 601	3	4.167	18	42		200		4,094		246		80			
		5	SR 2532 Glover Rd	SR 1002 (Old Concord Ch Rd) to Pvmt Jt at SR 2530 (Lippard Rd)	1	1.247	21	12	123	233		1,428		86		10			
		6	SR 2300 N Main St	US 52 (S. Salisbury Ave) to Granite Quarry CL	2	0.350	22	4		244		451		27		10			
		7	SR 1500 Roseman Rd	SR 1503 (Grace Ch Rd) to 2nd Pvmt Jt (at Stop Sign) at US 29	2	1.038	20	10				1,216		73		40			1
TOTAL FOR WORK ORDER NO. 9CR.20801.3						7.381		74	344	1,277	0	7,189	851	431	51	160	0	0	1
9CR.308008.3	Granite Quarry	8	SR 2300 N Main St	Granite Quarry SCL to SR 2385 (Balfour Quarry Rd)	2	0.522	22	5				672		40		10			
		8	SR 2300 N Main St	SR 2385 (Balfour Quarry Rd) to End of 2 ft Conc C&G, Just Past Depot St (NS)	6	0.639	24					836		50		10		10	4
		8	SR 2300 N Main St	End of 2 ft Conc C&G N of Depot St (NS) to Beg of 2 ft C&G at W Church St (NS)	7,8	0.360	25			1,267		499		30		10		1	2
		8	SR 2300 N Main St	2 ft Conc C&G at W Church St (NS) to Pvmt Jt N of Kerns St (NS)	6	0.415	24					543		33		10		3	2
TOTAL FOR WORK ORDER NO. 9CR.308008.3						1.936		5	0	1,267	0	2,550	0	153	0	40	1	13	8
9CR.308010.3	Landis	9	SR 1210 Old Beatty Ford Rd	Landis CL to US 29	1	0.120	22	1				144		9					
TOTAL FOR WORK ORDER NO. 9CR.308010.3						0.120		1	0	0	0	144	0	9	0	0	0	0	0
9CR.308014.3	Salisbury	10	SR 1703 Old Wilkesboro Rd	Partee St (NS) to End of C&G Both Sides above Brenner Ave (NS)	4,5	0.275	24		552			360		22		10		3	3
		11	SR 1703 Old Wilkesboro Rd	End of C&G Both Sides to Brenner Ave (NS) to End of C&G One Side at Linn Ln (NS)	9	0.153	27	2		300		225		14		8		1	1
		12	SR 1703 Old Wilkesboro Rd	End of One Side C&G at Linn Ln (NS) to McCoy Rd (NS)	1	0.693	20	7	396	222		807		48		10			
		13	SR 1703 W Monroe St	S Fulton St (NS) to Partee St (NS - West Side)	5	0.686	25		10,061			934		56		20			
		14	US 601/70 NB Jake Alexander Blvd	Median Section South of US 70 (Statesville Blvd)	13	0.095	48			200			256		15	50			
		14	US 601/70 SB Jake Alexander Blvd	US 70 (Statesville Blvd) to end of Median Section	12	0.095	24			200			124		7			1	
		14	US 601/70 Jake Alexander Blvd	Begin 5-Lane South of US 70 (Statesville Blvd) to South Bound Stop Bar at Brenner Ave (NS)	10	1.920	60						6,256		375	45		10	
		14	US 601/70 Jake Alexander Blvd	South Bound Stop Bar at Brenner Ave (NS) to South Bound Stop Bar at Lincolnton Ave (NS)	11	0.277	84		613				1,334		80	10		3	
		14	US 601/70 Jake Alexander Blvd	SB Stop Bar at Lincolnton Ave (NS) to Pvmt Jt on South Side of NC 150 (Mooresville Rd) Intersection	11	0.204	84		1000				1,061		64	10		3	
TOTAL FOR MAP NO. 14						2.591		0	1,613	400	0	0	9,031	0	542	115	0	17	0
TOTAL FOR WORK ORDER NO. 9CR.308014.3						4.398		9	12,622	922	0	2,326	9,031	140	542	163	0	21	4
9CR.308015.3	Spencer	15	SR 1915 Jefferson St	US 29/70 (Salisbury Ave) to SR 1915 (Whitehead Ave)	4	0.212	32			133		369		22		10		5	3
		15	SR 1915 Whitehead St	SR 1915 (Jefferson St) to SR 2026 (Oakwood Dr)	4,15	0.072	34			507		133		8		5			1
		15	SR 1915 Whitehead St	SR 2026 (Oakwood Dr) to End of Widening	4,15	0.197	60			500		642		39		10		4	
		15	SR 1915 Whitehead St	End of Widening to SR 1915/SR 2037 (3rd St)	4	0.176	32					307		18		8		1	2
TOTAL FOR MAP NO. 15						0.657		0	0	640	500	1,451	87	87	33	10	4	10	6
		16	SR 1912 7th St	US 29 (Salisbury Ave) to S Yadkin St (NS)	4	0.103	25					140		8		5		1	
		16	SR 1912 7th St	S Yadkin St (NS) to S Carolina St (NS)	4	0.134	18					132		8		8		2	
		16	SR 1912 7th St	S Carolina St (NS) to S Baldwin St (NS)	4	0.329	25					448		27		8		7	5
		16	SR 1912 7th St	S Baldwin St (NS) to Spencer NCL	1	0.328	18	3	383	200		322		19		10			
TOTAL FOR MAP NO. 16						0.894		3	383	200	0	1,042	0	63	0	31	0	10	5
TOTAL FOR WORK ORDER NO. 9CR.308015.3						1.551		3	383	840	500	2,493	0	150	0	64	0	20	11
TOTAL FOR 2005 CONTRACT RESURFACING						19.830		136	13,349	4,417	500	14,702	15,722	882	943	467	1	54	24