PROJECT REFERENCE NO.	SHEET NO.
R-2911C	EC-41/CONST. 18
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

NC GRID (NAD 1983)

MATCH TO SHEET 17 STA. 175+00.00 -L2-

MATCH TO SHEET 19 STA. 187+00.00 -L2-

CLYDE FLEMING GRAHAM AND W.F.LAVANCHE MAP BK.9995, PG.2165 (69)

ADA WILHELM FLEMING ETAL MAP BK.9995, PG.2165 (67)

CLYDE FLEMING GRAHAM FARM EQUIPMENT MAP BK.9995, PG.2165 (62A)

MINNIE PAULINE GRAHAM MAP BK.9995, PG.2165 (68)

CLYDE F. GRAHAM DB.663, PG.898 (70)

NOTE: PLACE PROPOSED BARBED WIRE FENCE BEFORE REMOVING EXISTING FENCE

20 x 10 x 3

BL-15 POT 172+45.40 BLL= POT 175+30.42 10.30 LT L2

BL-16 POT 182+28.66 BLL= POT 185+13.68, 11.72 LT L2

S 78° 30' 23.3"

S 11° 29' 36.7" W 567.24' (COR-COR)

S 11° 43' 56.5" W 50.17' (COR-COR)

S 11° 24' 19" W 672.50' (COR-COR)

N 11° 52' 50" E 682.00' (COR-COR)

US 70 STATESVILLE BLVD 28' BST

EXISTING R/W

5.15% FULL

150' TAPER

384.59' STORAGE

384.08' STORAGE

15" RCP

24" RCP

30" RCP

2GI-A FS SEE SHT. 2E

CAT-1

REMOVE

REMOVE HW

RESET GATE

END FENCE +58.80

PROP 5 STRAND BARBED WIRE FENCE

BEG FENCE +18.80

CLASS 'B' RIPRAP EST. 5 TONS RIPRAP EST 16 SY FILTER FABRIC

15" CSP W/ ELBOW

10' SOIL

10' GR

END FENCE +00.00

BEG FENCE +60.00

BERM DITCH

TSD

CONC

48"WW & 2SBW

+93.76 115.00' TIE TO EXIST. FENCE

+88.00 110.00' & 120.00'

180+00

185+00

DATE: $DATES
TIME: $TIMES
$FILES