


NOTES

THE BARRIER RAIL IN THE CONTINUOUS UNIT SHALL NOT BE CAST UNTIL ALL SLAB CONCRETE IN THE CONTINUOUS UNIT HAS BEEN CAST AND HAS REACHED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI.

ALL REINFORCING STEEL IN BARRIER RAILS SHALL BE EPOXY COATED.

VERTICAL GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE BARRIER RAIL AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN BARRIER RAIL EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF BARRIER RAIL SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.

BAR TYPES




ALL BAR DIMENSIONS ARE OUT TO OUT


BILL OF MATERIAL

FOR CONCRETE BARRIER RAIL ONLY

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
* B1	84	#5	STR	29'-7"	2592
* B2	28	#5	STR	28'-9"	840
* S1	480	#5	1	4'-8"	2336
* S2	480	#5	2	5'-2"	2587
* EPOXY COATED REINFORCING STEEL					8355 LBS.
CLASS AA CONCRETE					47.7 CU. YDS.
CONCRETE BARRIER RAIL					476.58 LIN. FT.




PLAN



SECTION THRU RAIL


END OF RAIL DETAILS



SECTION S-S


AT DAM IN OPEN JOINT
(THIS IS TO BE USED ONLY
WHEN SLIP FORM IS USED)

1/2" EXP. JT. MAT'L HELD IN PLACE WITH GALVANIZED NAILS.
(NOTE: OMIT EXP. JT. MAT'L. WHEN SLIP FORM IS USED.)



ELEVATION AT EXPANSION JOINTS

BARRIER RAIL DETAILS



PROJECT NO. R-2911D
ROWAN COUNTY
 STATION: 304+22.00-L-

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
CONCRETE BARRIER RAIL
 (LEFT LANE)

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-71	
1			3			TOTAL SHEETS	120
2			4				

STD. NO. CBRI

STR. #3

ASSEMBLED BY : S.H. SOCKWELL	DATE : 5/04
CHECKED BY : K.D. LAYNE	DATE : 5/04
DRAWN BY : ARB 5/87	REV. 8/16/99 RWW/LES
CHECKED BY : SJD 9/87	REV. 10/17/00 RWW/LES
	REV. 5/17/03R RWW/JTE