

### EARTHWORK SUMMARIES

PROJECT C201205 (R-2911D)

COUNTY Rowan

DATE 26-Jul-04

SHEET 1 OF 2 SHEETS

LINE	STATION STATION		TOTAL			UNCL. (UNCL.)		TOTAL	ROCK	EARTH	EMB.	BORROW	ROCK	SUITABLE	UNCL. (UNCL.)	TOTAL
			EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT EXCAV.	EXCAV. (UNCL.)	EXCAV. (UNCL.)									
L1	210+93.74	225+00.00	2,165	0	0	0	2,165	349	0	349	419	0	0	1,746	0	1,746
LLT	225+00.00	229+78.74	4	0	0	0	4	6,896	0	6,896	8,275	8,272	0	0	0	0
LLT	231+48.49	260+00.00	8,261	0	0	0	8,261	10,905	0	10,905	13,085	4,824	0	0	0	0
Y1rev	11+00.00	16+66.56	1,003	0	0	0	1,003	1,460	0	1,460	1,752	749	0	0	0	0
LLT	260+00.00	290+00.00	18,670	0	0	0	18,670	995	0	995	1,195	0	0	17,476	0	17,476
Y9	14+83.74	19+24.30	516	0	0	0	516	146	0	146	175	0	0	341	0	341
LLT	290+00.00	303+02.00	3,108	0	0	0	3,108	2,271	0	2,271	2,725	0	0	383	0	383
Y4	10+00.00	14+69.22	3,073	0	0	0	3,073	52	0	52	62	0	0	3,011	0	3,011
LLT	305+42.00	335+00.00	3,027	0	0	0	3,027	6,701	0	6,701	8,041	5,014	0	0	0	0
LLT	335+00.00	365+00.00	20,568	0	0	0	20,568	4,425	0	4,425	5,310	0	0	15,257	0	15,257
LLT	365+00.00	371+45.89	293	0	0	0	293	225	0	225	270	0	0	23	0	23
<b>SUBTOTAL #1</b>			<b>60,688</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>60,688</b>	<b>34,425</b>	<b>0</b>	<b>34,425</b>	<b>41,310</b>	<b>18,859</b>	<b>0</b>	<b>38,237</b>	<b>0</b>	<b>38,237</b>
L2	210+93.47	225+00.00	2,187	0	0	0	2,187	10,827	0	10,827	12,992	10,805	0	0	0	0
LRT	225+00.00	230+87.26	0	0	0	0	0	27,053	0	27,053	32,463	32,463	0	0	0	0
Y15	10+47.00	15+31.42	66	0	0	0	66	13,127	0	13,127	15,753	15,687	0	0	0	0
<b>SHEET TOTALS:</b>																