

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

**SUMMARY OF
WOVEN WIRE FENCE**

LINE	STATION	STATION	LT OR RT	47" FABRIC FT	4" TIMBER POST	5" TIMBER POST	LINE	STATION	STATION	LT OR RT	47" FABRIC FT	4" TIMBER POST	5" TIMBER POST
L	211+89.09	214+57.92	LT	269	17	4	L	361+75.75	363+39.54	LT	164	8	7
L	215+18.66	215+80.66	LT	62	2	4	L2	217+90.61	219+50.87	RT	163	9	4
L	216+41.40	217+26.11	LT	85	4	4	L2	220+10.14	224+80.76	RT	475	27	13
L	218+46.33	220+76.24	LT	230	14	4	L	227+87.73	230+68.86	RT	312	20	5
L	221+36.24	225+00.00	LT	364	22	8	Y8	14+04.01	14+43.60	RT	30	1	2
L	225+00.00	228+55.10	LT	355	20	9	Y8	16+17.65	17+05.60	LT	65	2	5
Y8	11+44.71	12+18.73	RT	74	4	2	L	223+80.64	245+43.73	RT	2,163	139	29
Y8	13+92.59	14+22.40	LT	30	1	2	L	246+91.17	251+69.50	RT	478	25	16
L	231+50.07	245+69.40	LT	1,419	90	20	L	252+91.10	254+89.26	RT	198	10	7
L	246+90.49	253+50.00	LT	660	39	14	L	255+17.03	263+50.00	RT	833	44	28
L	253+50.00	253+86.71	LT	37	0	5	L	264+11.62	265+88.59	RT	177	10	4
L	254+20.89	263+90.00	LT	969	52	31	L	266+51.21	272+20.70	RT	569	25	28
L	264+50.00	269+13.30	LT	463	26	13	L	273+46.37	292+90.76	RT	1,944	119	37
L	272+89.13	280+33.37	LT	744	43	19	L	293+83.26	295+15.74	RT	132	7	4
L	280+93.37	292+64.47	LT	1,171	73	20	L	295+77.68	303+00.00	RT	722	36	28
Y4	14+01.21	14+43.03	RT	42	0	5	L	305+55.00	313+92.26	RT	837	51	16
Y4	13+48.54	13+83.68	LT	35	0	5	L	314+52.26	318+35.31	RT	383	22	10
L	294+74.90	296+52.60	LT	178	12	2	L	318+95.31	362+30.12	RT	735	45	13
L	297+11.52	303+02.00	LT	590	33	16	L	326+78.15	330+07.99	RT	330	18	10
L	305+40.68	314+40.00	LT	899	52	22	L	330+73.17	335+77.70	RT	505	31	10
L	315+00.00	319+10.00	LT	410	24	10	L	336+37.01	341+16.06	RT	479	28	11
L	319+70.00	325+00.00	LT	530	32	10	Y5	11+14.54	11+68.17	RT	54	3	2
L	325+60.26	331+25.87	LT	566	32	16	Y5	11+10.48	11+73.52	LT	63	2	5
L	349+00.00	349+60.00	LT	60	1	7	L	343+89.73	353+90.00	RT	1,000	64	14
L	352+35.37	353+70.59	LT	135	8	4	L	354+50.00	359+32.35	RT	482	24	19
L	354+21.59	357+71.03	LT	349	20	10	L	359+60.59	361+36.85	RT	176	9	7
L	358+31.04	359+53.51	LT	122	7	4	L	361+96.16	363+52.84	RT	157	7	7
L	359+81.61	361+14.89	LT	133	6	7							
									TOTAL:		24,609	1,421	618
									SAY:		24,610	1,425	620

**SUMMARY OF
4 STRAND
BARBED WIRE FENCE**

LINE	STATION	STATION	LT OR RT	LINEAR FEET	LINE POST	TERM POST
L	342+21.23	343+90.88	LT	170	9	6
L	346+59.04	348+06.89	LT	148	7	6
				TOTAL:	317	12
				SAY:	320	12

**SUMMARY OF
5 STRAND
BARBED WIRE FENCE**

LINE	STATION	STATION	LT OR RT	LINEAR FEET	LINE POST	TERM POST
L	232+49.24	242+75.19	LT	1,026	63	18
				TOTAL:	1,026	18
				SAY:	1,050	18

**SUMMARY OF
PAVEMENT BREAK-UP**

LINE	STATION	STATION	LOC LT/RT /CL	YD ²
L	223+50.00	225+00.00	CL	400
L	225+00.00	229+78.74	LT	1,276
L	231+48.49	238+00.00	LT	1,737
L	252+00.00	254+50.00	LT	666
L	305+42.00	308+50.00	LT	821
L	317+50.00	323+50.00	LT	1,600
L	329+00.00	331+50.00	LT	666
L	352+00.00	360+50.00	LT	2,266
			TOTAL:	9,432
			SAY:	9,500

**SUMMARY OF
PAVEMENT REMOVAL**

LINE	STATION	STATION	LOC LT/RT /CL	YD ²
L	220+50.00	221+55.00	RT	210
L2	221+25.00	225+85.00	RT	1,025
Y15	10+80.00	14+05.00	LT	873
L	238+20.00	244+32.00	LT	1,214
L	237+10.00	245+45.00	CL	1,109
Y2REV	10+63.00	12+22.00	RT	554
L	12+37.00	14+78.00	LT	681
L	251+00.00	261+10.00	CL	1,369
L	251+97.00	252+75.00	RT	565
L	265+05.00	272+00.00	CL	485
L	266+25.00	271+50.00	LT	856
L	326+53.00	330+52.00	CL	817
L	332+63.00	341+90.00	CL	1,018
L	359+60.00	363+54.00	CL	325
L	364+38.00	370+35.00	CL	868
L	275+00.00	291+00.00	LT	4,266
L	295+50.00	303+02.00	LT	2,005
L	338+00.00	350+00.00	LT	3,200
Y5DET	09+83.74	14+43.00	CL	1,122
Y5DET	14+43.00	15+63.00	CL	146
			GEOTECH CONTINGENCY	500
			TOTAL:	23,208
			SAY:	23,300