

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200928														
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	169300000-E	654	40	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	468600000-E	1205	3,100	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+05.00)	200000000-N	806	26	EA	RIGHT OF WAY MARKERS	490000000-N	1252	40	EA	PERMANENT RAISED PAVEMENT MARKERS
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	220900000-E	838	2.8	CY	ENDWALLS	600000000-E	1605	1,650	LF	TEMPORARY SILT FENCE
005700000-E	226	70	CY	UNDERCUT EXCAVATION	228600000-N	840	6	EA	MASONRY DRAINAGE STRUCTURES	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
006300000-N	SP	Lump Sum		GRADING	236600000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.24	600900000-E	1610	525	TON	STONE FOR EROSION CONTROL, CLASS B
008000000-E	SP	50	TON	CLASS IV SUBGRADE STABILIZATION	236700000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29	601200000-E	1610	275	TON	SEDIMENT CONTROL STONE
010600000-E	230	14,800	CY	BORROW EXCAVATION	239600000-N	840	1	EA	FRAME WITH COVER, STD 840.54	601500000-E	1615	5	ACR	TEMPORARY MULCHING
013400000-E	240	265	CY	DRAINAGE DITCH EXCAVATION	255600000-E	846	455	LF	SHOULDER BERM GUTTER	601800000-E	1620	200	LB	SEED FOR TEMPORARY SEEDING
019500000-E	265	40	CY	SELECT GRANULAR MATERIAL	303000000-E	862	1,087.5	LF	STEEL BM GUARDRAIL	602100000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEEDING
019600000-E	270	40	SY	FABRIC FOR SOIL STABILIZATION	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	602400000-E	1622	265	LF	TEMPORARY SLOPE DRAINS
031800000-E	300	63	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	602700000-N	1622	5	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
034300000-E	310	80	LF	15" SIDE DRAIN PIPE	327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	602900000-E	SP	500	LF	SAFETY FENCE
036600000-E	310	96	LF	15" RC PIPE CULVERTS, CLASS III	364900000-E	876	90	TON	PLAIN RIP RAP, CLASS B	603000000-E	1630	1,400	CY	SILT EXCAVATION
039000000-E	310	188	LF	36" RC PIPE CULVERTS, CLASS III	365600000-E	876	650	SY	FILTER FABRIC FOR DRAINAGE	603600000-E	1631	1,800	SY	MATTING FOR EROSION CONTROL
070800000-E	310	228	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	365900000-N	SP	3	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	603800000-E	SP	230	SY	PERMANENT SOIL REINFORCEMENT MAT
080600000-E	310	6	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	402500000-E	901	16.25	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	604200000-E	1632	100	LF	1/4" HARDWARE CLOTH
099500000-E	340	41	LF	PIPE REMOVAL	407200000-E	903	40	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	607000000-N	SP	6	EA	SPECIAL STILLING BASINS
112100000-E	520	210	TON	AGGREGATE BASE COURSE	410200000-N	904	3	EA	SIGN ERECTION, TYPE E	608400000-E	1660	6	ACR	SEEDING & MULCHING
122000000-E	545	75	TON	INCIDENTAL STONE BASE	415000000-N	907	10	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	608700000-E	1660	3	ACR	MOWING
148900000-E	610	932	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	440000000-E	1110	348	SF	WORK ZONE SIGNS (STATIONARY)	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
149800000-E	610	767	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	441000000-E	1110	114	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
152500000-E	SP	901	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	442500000-N	1125	2	EA	WARNING FLAG SETS	609600000-E	1662	125	LB	SEED FOR SUPPLEMENTAL SEEDING
156000000-E	620	135	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	443000000-N	1130	25	EA	DRUMS	610800000-E	1665	4.5	TON	FERTILIZER TOPDRESSING
					444500000-E	1145	128	LF	BARRICADES (TYPE III)	611400000-N	SP	3	HR	SPECIALIZED HAND MOWING
					468500000-E	1205	3,100	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL