

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM ROADWAY CONSTRUCTION	Lump Sum	L.S.	
<b>STRUCTURE ITEMS</b>						
0003	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+05.00 -L-)	Lump Sum	L.S.	
0004	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+05.00 -L-)	Lump Sum	L.S.	
0005	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	25 LF		
0006	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	26 LF		
0007	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	20 LF		
0008	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0009	8116000000-E	SP	CSL TUBES	244 LF		
0010	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,520 CY		
0011	8364000000-E	450	HP12X53 STEEL PILES	395 LF		
0012	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	920 TON		
0013	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	
0014	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	

C200928 (B-3704)  
WAKE COUNTY

2/16/99

Contract No: C200928

Counties: Wake

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General