

DIVISION OF HIGHWAYS
 STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK

LOCATION	UNCLASSIFIED EXCAVATION	EMBANKMENT +%	BORROW	WASTE
PHASE 1 - DETOUR PLACEMENT				
-DET- STA. 12+09.67 TO -DET- STA. 18+02.00	32	3726	3694	0
-DET- STA. 19+12.00 TO -DET- STA. 24+64.04	43	3020	2977	0
SUMMARY NO. 1 TOTAL	75	6746	6671	0
PHASE 2 - MAINLINE CONSTRUCTION				
-L- STA. 12+00 TO -L- STA. 17+98.50	8	1906	1898	0
-L- STA. 19+08.50 TO -L- STA. 25+00.00	1	1695	1694	0
SUMMARY NO. 2 TOTAL	9	3601	3592	0
PHASE 3 - DETOUR REMOVAL				
-L- STA. 12+50.00 TO -L- STA. 17+98.50	2301	277	0	2024
-L- STA. 19+08.50 TO -L- STA. 25+00.00	2141	192	0	1949
SUMMARY NO. 3 TOTAL	4442	469	0	3973
SUMMARIES TOTAL	4526	10816	10263	3973
EST. 5% FOR REPLACEMENT OF				
TOPSOIL AT BORROW PIT			513	
PROJECT TOTAL	4526		10776	3973
SAY	4600		10800	4010
ESTIMATED UNDERCUT	500 CY			

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE FRADING, CLEARING & GRUBBING AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE LUMP SUM PRICE FOR "GRADING".

ASPHALT PAVEMENT REMOVAL SUMMARY

LOCATION DESCRIPTION	ASPHALT REMOVAL Sq. Yd.	ASPHALT BREAK-UP Sq. Yd.
-L- STA. 14+35.00 TO -L- STA. 18+02.47	980	
-L- STA. 19+04.82 TO -L- STA. 22+25.00	854	
-DET- STA. 12+63.34 TO -DET- STA. 18+02.00	1110	
-DET- STA. 19+12.00 TO -DET- STA. 24+14.63	1022	
PROJECT TOTAL	3966	
SAY	3975	