

6/4/99

COMPUTED BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
CHECKED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

PROJECT REFERENCE NO. B-3711  
SHEET NO. 3

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201123

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	538400000-E	1510	184	LF	16" DI WATER PIPE, PC ***** (PC250)
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	548000000-E	1510	1,360	LB	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+53.50 -L-)	588200000-N	SP	16	EA	GENERIC UTILITY ITEM 16" RESTRAINED RETAINER GLANDS
004300000-N	226	Lump Sum		GRADING	588800000-E	SP	280	LF	GENERIC UTILITY ITEM 20" HDPE WATER PIPE BY DIRECTIONAL BORE
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	600000000-E	1605	960	LF	TEMPORARY SILT FENCE
005700000-E	226	500	CY	UNDERCUT EXCAVATION	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
019500000-E	265	200	CY	SELECT GRANULAR MATERIAL	600900000-E	1610	465	TON	STONE FOR EROSION CONTROL, CLASS B
019600000-E	270	200	SY	FABRIC FOR SOIL STABILIZATION	601200000-E	1610	150	TON	SEDIMENT CONTROL STONE
031800000-E	300	7	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	601500000-E	1615	4	ACR	TEMPORARY MULCHING
070800000-E	310	68	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	601800000-E	1620	150	LB	SEED FOR TEMPORARY SEEDING
080600000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	602100000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEEDING
112100000-E	520	950	TON	AGGREGATE BASE COURSE	602400000-E	1622	200	LF	TEMPORARY SLOPE DRAINS
122000000-E	545	100	TON	INCIDENTAL STONE BASE	602700000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
127500000-E	600	810	GAL	PRIME COAT	602900000-E	SP	200	LF	SAFETY FENCE
148900000-E	610	520	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	603000000-E	1630	870	CY	SILT EXCAVATION
149800000-E	610	425	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	603600000-E	1631	1,485	SY	MATting FOR EROSION CONTROL
151900000-E	610	1,120	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	604200000-E	1632	40	LF	1/4" HARDWARE CLOTH
156000000-E	620	110	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	608400000-E	1660	5	ACR	SEEDING & MULCHING
200000000-N	806	12	EA	RIGHT OF WAY MARKERS	608700000-E	1660	2.5	ACR	MOWING
228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
255600000-E	846	55	LF	SHOULDER BERM GUTTER	609600000-E	1662	100	LB	SEED FOR SUPPLEMENTAL SEEDING
303000000-E	862	650	LF	STEEL BM GUARDRAIL	610800000-E	1665	3.75	TON	FERTILIZER TOPDRESSING
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	610920000-E	SP	0.1	ACR	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (CENTIPEDE)
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	611400000-N	SP	2	HR	SPECIALIZED HAND MOWING
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
338000000-E	862	325	LF	TEMPORARY STEEL BM GUARDRAIL	612300000-E	1670	1.3	ACR	REFORESTATION
338700000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)					
338910000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY					
364900000-E	876	2	TON	PLAIN RIP RAP, CLASS B					
365600000-E	876	160	SY	FILTER FABRIC FOR DRAINAGE					
440000000-E	1110	124	SF	WORK ZONE SIGNS (STATIONARY)					
440500000-E	1110	96	SF	WORK ZONE SIGNS (PORTABLE)					
441000000-E	1110	72	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)					
443000000-N	1130	50	EA	DRUMS					
443500000-N	1135	30	EA	CONES					
444500000-E	1145	48	LF	BARRICADES (TYPE III)					
445500000-N	1150	24	MD	FLAGGER					
465000000-N	1251	69	EA	TEMPORARY RAISED PAVEMENT MARKERS					
468500000-E	1205	2,760	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)					
468600000-E	1205	2,760	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)					
481000000-E	1205	11,040	LF	PAINT PAVEMENT MARKING LINES (4")					
485000000-E	1205	2,920	LF	REMOVAL OF PAVEMENT MARKING LINES (4")					
490000000-N	1252	18	EA	PERMANENT RAISED PAVEMENT MARKERS					
530000000-E	1505	10	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)					
530600000-E	SP	10	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)					

12-JUL-2004 10:44  
C:\Pro1\B3711\_r.dwg Summer1.es.dgn  
TLBelle AT RD206440