

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS

INDEX OF SHEETS

GENERAL NOTES

LIST OF STANDARD DRAWINGS

INDEX OF SHEETS

1	Title Sheet
1-A	Index of Sheets, General Notes, Lists of Standards
1-B	Symbology Sheet
1-C	Survey Control Plan Sheet
2 thru 2-A	Pavement Schedule, Typical Sections, and Miscellaneous Details
2-B thru 2-E	Guardrail Installation Details
2-F thru 2-G	Structure Anchor Units Details
2-H thru 2-I	Reinforced Bridge Approach Fills
3	Summary of Quantities
3-A thru 3-B	Drainage Summaries, Guardrail Summary, Earthwork Summary, Pavement Removal Summary, and Breaking of Asphalt Summary
3-C	Parcel Index Sheet
4 thru 7	Plan Sheets
8 thru 9	Profile Sheets
TCP-1 thru TCP-5	Traffic Control Plan Sheets
EC-1 thru EC-10	Erosion Control Plan Sheets
RF-1	Reforestation Plans
UC-1 thru UC-2	Utility Construction Plan Sheets
UO-1 thru UO-2	Utility Conflict Plans
XA-1	Cross Section Summary Sheets
X-1 thru X-5	Cross Sections
S-1 thru S-16	Structure Plans

GENERAL NOTES:

2002 SPECIFICATIONS
 EFFECTIVE: 01-15-02

**GRADE LINE:
 GRADING AND SURFACING OR RESURFACING AND WIDENING:**

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT AND EARTH SHOULDER CONSTRUCTION ON HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC WILL BE PAID FOR AS "EXTRA WORK" IN ACCORDANCE WITH SECTION 104-7.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE: TRI COUNTY EMC, SOUTHERN BELL

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS, EXCEPT AS SHOWN ON THE PLANS.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACTOR.

EFF. 01-15-02

ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January 15, 2002 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO. TITLE

DIVISION 2 - EARTHWORK

200.03	Method of Clearing - Method III
225.02	Guide for Grading Subgrade - Secondary and Local
225.04	Method of Obtaining Superelevation - Two Lane Pavement

DIVISION 3 - PIPE CULVERTS

300.01	Method of Pipe Installation - Method 'A'
--------	--

DIVISION 5 - SUBGRADE, BASES AND SHOULDERS

560.01	Method of Shoulder Construction - High Side of Superelevated Curve - Method I
--------	---

DIVISION 8 - INCIDENTALS

806.01	Concrete Right-of-Way Marker
806.02	Granite Right-of-Way Marker
820.04	Drain Installation in Shoulder Berm Gutter
840.00	Concrete Base Pad for Drainage Structures
840.25	Anchorage for Frames - Brick or Concrete
840.29	Frames and Narrow Slot Flat Grates
840.35	Traffic Bearing Drop Inlet - for Cast Iron Double Frame and Grates
840.46	Traffic Bearing Precast Drainage Structure
840.66	Drainage Structure Steps
846.01	Concrete Curb, Gutter and Curb & Gutter
862.01	Guardrail Placement
876.02	Guide for Rip Rap at Pipe Outlets