

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

STATE PROJECT REFERENCE NO.	SHEET NO.
B-3711	TCP-1

**PLAN FOR PROPOSED  
TRAFFIC CONTROL, MARKING & DELINEATION  
WAYNE COUNTY**

B-3711

**ROADWAY STANDARD DRAWINGS**

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS"- ROADWAY DESIGN UNIT-N.C. DEPARTMENT OF TRANSPORTATION-RALEIGH, N.C., DATED JANUARY 2002 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.02	TEMPORARY LANE CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1110.02	PORTABLE WORK ZONE SIGNS
1135.01	CONES
1145.01	BARRICADES
1150.01	FLAGGERS
1205.01	PAVEMENT MARKINGS - LINE TYPES & OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE & MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1250.01	PAVEMENT MARKER SPACING
1251.01	RAISED PAVEMENT MARKERS (TEMPORARY & PERMANENT)
1261.01	GUARDRAIL & BARRIER DELINEATOR SPACING
1261.02	GUARDRAIL & BARRIER DELINEATOR TYPES
1262.01	GUARDRAIL END DELINEATION

**INDEX OF SHEETS**

SHEET NO.	TITLE
TCP-1	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, PHASING, TEMPORARY AND FINAL PAVEMENT MARKING SCHEDULES, AND INDEX OF SHEETS
TCP-2	GENERAL NOTES AND PHASING
TCP-3 THRU 4	PHASE I & II DETAIL SHEETS
TCP-5	REPLACEMENT DETAIL FOR RSD 1130.01

**LEGEND**

- GENERAL**
- DIRECTION OF TRAFFIC FLOW
  - NORTH ARROW
  - PROPOSED PVMT. EXIST. PVMT.
  - WORK AREA
  - REMOVAL OF EXISTING PAVEMENT

**TRAFFIC CONTROL DEVICES**

- TYPE I BARRICADE
- TYPE II BARRICADE
- TYPE III BARRICADE
- CONE
- DRUM
- FLASHING ARROW PANEL (TYPE C)
- TYPE 'B' WARNING LIGHT
- STATIONARY SIGN
- PORTABLE SIGN
- STATIONARY OR PORTABLE SIGN
- WARNING FLAGS
- CRASH CUSHION
- CHANGEABLE MESSAGE SIGN
- TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)
- POLICE
- FLAGGER

**PAVEMENT MARKINGS**

- CRYSTAL/CRYSTAL PAVEMENT MARKER
- YELLOW/YELLOW PAVEMENT MARKER
- CRYSTAL/RED PAVEMENT MARKER
- PAVEMENT MARKING SYMBOLS

Final Pavement Marking Schedule				
SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY BREAKDOWN	TOTAL QUANTITY
PAVEMENT MARKINGS				
TA	WHITE EDGELINE	THERMOPLASTIC (4", 90 MILS)	2760 LF	
			TOTAL	2760 LF
TI	YELLOW DOUBLE CENTER	THERMOPLASTIC (4", 120 MILS)	2760 LF	
			TOTAL	2760 LF
PERMANENT RAISED PAVEMENT MARKERS				
MA	YELLOW & YELLOW		18 EA	
			TOTAL	18 EA
Temporary Pavement Marking Schedule				
SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY BREAKDOWN	TOTAL QUANTITY
PAVEMENT MARKINGS				
PAINT (4")				
PA	WHITE EDGELINE (2X)		5520 LF	
PI	YELLOW DOUBLE CENTER (2X)		5520 LF	
			TOTAL	11040 LF
TEMPORARY RAISED PAVEMENT MARKERS				
MK	YELLOW & YELLOW		69 EA	
			TOTAL	69 EA

APPROVED: *Jessica Kuse*  
DATE: 8/28/04

PLAN PREPARED BY: N.C.D.O.T. TRAFFIC CONTROL, MARKING & DELINEATION SECTION

SEAL



J.S. BOURNE, P.E. **TRAFFIC CONTROL ENGINEER**  
J.S. KITE, P.E. **TRAFFIC CONTROL PROJECT ENGINEER**  
J.D. KUSE, P.E. **TRAFFIC CONTROL PROJECT DESIGN ENGINEER**  
D.A. HAYES, E.I. **TRAFFIC CONTROL DESIGN ENGINEER / TECHNICIAN**

TIP PROJECT: