

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+53.50 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	7 TON		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	68 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0012	1121000000-E	520	AGGREGATE BASE COURSE	950 TON		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1275000000-E	600	PRIME COAT	810 GAL		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	520 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	425 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,120 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	110 TON		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
0020	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0022	2556000000-E	846	SHOULDER BERM GUTTER	55 LF		
0023	3030000000-E	862	STEEL BM GUARDRAIL	650 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0025	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0026	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0027	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	325 LF		
0028	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0029	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0030	3649000000-E	876	PLAIN RIP RAP, CLASS B	2 TON		
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	160 SY		
0032	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	124 SF		
0033	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	96 SF		
0034	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	72 SF		
0035	4430000000-N	1130	DRUMS	50 EA		
0036	4435000000-N	1135	CONES	30 EA		
0037	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4455000000-N	1150	FLAGGER	24 MD		
0039	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	69 EA		
0040	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,760 LF		
0041	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,760 LF		
0042	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,040 LF		
0043	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,920 LF		
0044	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	18 EA		
0045	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	10 TON		
0046	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	10 TON		
0047	5384000000-E	1510	16" DI WATER PIPE, PC ***** (PC250)	184 LF		
0048	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	1,360 LB		
0049	5882000000-N	SP	GENERIC UTILITY ITEM 16" RESTRAINED RETAINER GLANDS	16 EA		
0050	5888000000-E	SP	GENERIC UTILITY ITEM 20" HDPE WATER PIPE BY DIRECTIONAL BORE	280 LF		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	960 LF		
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	465 TON		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	150 TON		
0055	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0056	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0058	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0059	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0060	6029000000-E	SP	SAFETY FENCE	200 LF		
0061	6030000000-E	1630	SILT EXCAVATION	870 CY		
0062	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,485 SY		
0063	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0064	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0065	6087000000-E	1660	MOWING	2.5 ACR		
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	3.75 TON		
0070	6109200000-E	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (CENTI- PEDE)	0.1 ACR		
0071	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0072	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6123000000-E	1670	REFORESTATION	1.3 ACR		
<b>STRUCTURE ITEMS</b>						
0074	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (18+53.50 -L-)	Lump Sum	L.S.	
0075	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+53.50 -L-)	Lump Sum	L.S.	
0076	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+53.50 -L-)	Lump Sum	L.S.	
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	46.8 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+53.50 -L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,720 LB		
0080	8364000000-E	450	HP12X53 STEEL PILES	540 LF		
0081	8384000000-E	450	HP14X73 STEEL PILES	810 LF		
0082	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (18+53.50 -L-)	Lump Sum	L.S.	
0083	8503000000-E	460	CONCRETE BARRIER RAIL	215.5 LF		
0084	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	249 TON		
0085	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	277 SY		
0086	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,290 LF		

1448/Nov18/Q44049.95/D400610100000/E87

Total Amount Of Bid For Entire Project :

C201123 (B-3711)  
WAYNE COUNTY

2/16/99

Contract No: C201123

County: Wayne

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General