

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200843

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	443500000-N	1135	22	EA	CONES
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	444500000-E	1145	48	LF	BARRICADES (TYPE III)
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (10+87.50-L-)	228600000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES	445500000-N	1150	180	MD	FLAGGER
004300000-N	226	Lump Sum		GRADING	236700000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29	446000000-N	1155	4	EA	WARNING LIGHTS (TYPE B)
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	255600000-E	846	20	LF	SHOULDER BERM GUTTER	450700000-E	SP	25	LF	WATER FILLED BARRIER
019900000-E	SP	600	SF	TEMPORARY SHORING	303000000-E	862	25	LF	STEEL BM GUARDRAIL	473000000-E	1205	2,288	LF	EPOXY PAVEMENT MARKING LINES (4")
031800000-E	300	20	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	304500000-E	862	75	LF	STEEL BM GUARDRAIL, SHOP CURVED	475500000-E	1205	15	LF	EPOXY PAVEMENT MARKING LINES (24")
034300000-E	310	44	LF	15" SIDE DRAIN PIPE	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	481000000-E	1205	4,576	LF	PAINT PAVEMENT MARKING LINES (4")
037200000-E	310	76	LF	18" RC PIPE CULVERTS, CLASS III	318000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (III)	483500000-E	1205	30	LF	PAINT PAVEMENT MARKING LINES (24")
037800000-E	310	44	LF	24" RC PIPE CULVERTS, CLASS III	319500000-N	862	3	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	485000000-E	1205	400	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
072000000-E	310	24	LF	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	321500000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE III	600000000-E	1605	800	LF	TEMPORARY SILT FENCE
080800000-E	310	2	EA	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	327000000-N	SP	1	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
099500000-E	340	110	LF	PIPE REMOVAL	353300000-E	866	300	LF	CHAIN LINK FENCE, *** FABRIC (72")	600900000-E	1610	200	TON	STONE FOR EROSION CONTROL, CLASS B
112100000-E	520	32	TON	AGGREGATE BASE COURSE	353900000-E	866	25	EA	METAL LINE POSTS FOR *** CHAIN LINK FENCE (72")	601200000-E	1610	60	TON	SEDIMENT CONTROL STONE
122000000-E	545	100	TON	INCIDENTAL STONE BASE	354500000-E	866	5	EA	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (72")	601500000-E	1615	0.5	ACR	TEMPORARY MULCHING
148900000-E	610	690	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	355700000-E	866	50	LF	ADDITIONAL BARBED WIRE	601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
151400000-E	610	270	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5A	356400000-E	866	2	EA	SINGLE GATES, *** HIGH, ** WIDE, ** OPENING (72", 8', 8')	602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
156000000-E	620	48	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	364900000-E	876	1	TON	PLAIN RIP RAP, CLASS B	602400000-E	1622	55	LF	TEMPORARY SLOPE DRAINS
169300000-E	654	35	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	365600000-E	876	305	SY	FILTER FABRIC FOR DRAINAGE	602700000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
200000000-N	806	13	EA	RIGHT OF WAY MARKERS	440000000-E	1110	84	SF	WORK ZONE SIGNS (STATIONARY)	603000000-E	1630	175	CY	SILT EXCAVATION
202200000-E	815	23	CY	SUBDRAIN EXCAVATION	440500000-E	1110	96	SF	WORK ZONE SIGNS (PORTABLE)	603600000-E	1631	530	SY	MATting FOR EROSION CONTROL
203300000-E	815	17	CY	SUBDRAIN FINE AGGREGATE	441000000-E	1110	20	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	604200000-E	1632	20	LF	1/4" HARDWARE CLOTH
204400000-E	815	100	LF	6" PERFORATED SUBDRAIN PIPE	443000000-N	1130	40	EA	DRUMS	608400000-E	1660	0.5	ACR	SEEDING & MULCHING
205500000-E	815	3	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS						608700000-E	1660	0.5	ACR	MOWING
										609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
										609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
										609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
										610800000-E	1665	0.5	TON	FERTILIZER TOPDRESSING
										611400000-N	SP	0.5	HR	SPECIALIZED HAND MOWING
										611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
										612600000-E	SP	0.15	ACR	STREAMBANK REFORESTATION

5/28/99

09/23/03 14:15:07 b3607\_rdy\_sum.dgn