



FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM/QUANTITY BREAKDOWN	TOTAL QUANTITY
<u>PAVEMENT MARKING LINES</u>			
<u>THERMOPLASTIC (4", 120 MILS)</u>			
TD	WHITE MINI SKIP	34 LF	
TE	WHITE SOLID LANE LINE	106 LF	
TF	10 FT YELLOW SKIP	86 LF	
TH	YELLOW SINGLE CENTER	344 LF	
TI	YELLOW DOUBLE CENTER	620 LF	
			TOTAL 1190 LF
<u>THERMOPLASTIC (24", 120 MILS)</u>			
T2	WHITE STOP BAR	36 LF	
			TOTAL 36 LF
<u>PAVEMENT MARKING SYMBOLS</u>			
UA	LEFT TURN ARROW	8 EA	
			TOTAL 8 EA
<u>PAVEMENT MARKERS</u>			
MH	YELLOW & YELLOW	26 EA	
MI	CRYSTAL & RED	6 EA	
			TOTAL 32 EA

18-FEB-2004 14:03
 N:\VCP\Project\B-3475\15\01\01.dgn
 GenRad.dgn AT: TELC206432

APPROVED: <i>[Signature]</i>	DATE: 2/19/04	PAVEMENT MARKING PLAN	
	SCALE: NONE		
	DATE: 02/03		
	DWG. BY: VJR/DER		
	DESIGN BY: VJR/DER		
REVIEWED BY: MJH		REVISIONS	