

PROJECT NO.	SHEET NO.	TOTAL NO.
37445, ETC.	7	8

### SUMMARY OF QUANTITIES

PROJECT NO.	COUNTY	MAP NO.	ROUTE	DESCRIPTION	TYP	LENGTH MI	WIDTH FT	GRADING LS	FRAME, GRATE, & HOOD, STD 840.03 EA	FOUNDATION CONDITIONING MATERIAL TON	15" RC PIPE CULVERT, CLASS III LF	18" RC PIPE CULVERT, CLASS III LF	24" RC PIPE CULVERT, CLASS III LF	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	MILLING 2.5" SY	MILLING 1.5" TO 6" SY	BASE COURSE, B25.0B TONS	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	CONCRETE ENDWALL, STD. 838.01 CY	MASONRY DRAINAGE STRUCTURE EA	2'-6" CURB & GUTTER LF	WHEELCHAIR RAMPS EA	METER OR VALVE BOX EA	GUARDRAIL LF	GRAU, TYPE 350 EA	SEED & MULCHING AC	
37445	Hertford	1	NC461	FROM US13 TO WCL WINTON	1	1.2	28			10		96		120	2.4	16,896		1,082	3,135	1,837	304	22	2								2
<b>TOTAL FOR PROJ NO. 37445</b>						<b>1.2</b>				<b>10</b>		<b>96</b>		<b>120</b>	<b>2.4</b>	<b>16,896</b>		<b>1,082</b>	<b>3,135</b>	<b>1,837</b>	<b>304</b>	<b>22</b>	<b>2</b>							<b>2</b>	
37447	Hertford	2	NC45	FROM ECL WINTON TO SR 1403	2	1.9	28							190	3.8			2,483	1,310	2,910	343								812.50	18	2
		3	NC45	SR1403 TO SR 1427	3	0.4	30-36							40		1,800			718	43					136						
		4	NC45	SR 1427 TO NC 461	4	1.5	28	1		5			40	150	3			2,941	1,566	2,469	348					1		350	11	2	
		5	NC45	FROM NC 461 TO NEAR SR 1443 (BEGIN BRIDGE NO. 23)	5	3.3	26			5			48	330	6.6			4,063	1,943	4,899	560	11	1.5					662.50	14	5	
		6	NC45	FROM NEAR SR 1443 (END BRIDGE NO. 23) TO WCL HARRELLSVILLE	5	2.2	26							220	4.4			2,429	1,275	3,130	352							200	4	1.50	
		7	NC45	FROM WCL HARRELLSVILLE TO ECL HARRELLSVILLE	6	0.6	21-43		5	8	80			60	1.20		14,080			1,045	63			5	6,336	3					
		8	NC45	ECL HARRELLSVILLE TO BERTIE CO. LINE	5	4.4	26							440	8.8			4,859	2,549	6,261	704							1,625	22		
<b>TOTAL FOR PROJ NO. 37447</b>						<b>14.3</b>		<b>1</b>	<b>5</b>	<b>18</b>	<b>80</b>	<b>0</b>	<b>88</b>	<b>1,430</b>	<b>27.8</b>	<b>15,880</b>	<b>16,775</b>	<b>8,633</b>	<b>21,432</b>	<b>2,413</b>	<b>11</b>	<b>1.5</b>	<b>5</b>	<b>6,472</b>	<b>3</b>	<b>1</b>	<b>3,650</b>	<b>69</b>	<b>10.5</b>		
<b>GRAND TOTAL</b>						<b>15.5</b>		<b>1</b>	<b>5</b>	<b>28</b>	<b>80</b>	<b>96</b>	<b>88</b>	<b>1,550</b>	<b>30.20</b>	<b>16,896</b>	<b>15,880</b>	<b>17,857</b>	<b>11,768</b>	<b>23,269</b>	<b>2,717</b>	<b>33</b>	<b>3.5</b>	<b>5</b>	<b>6,472</b>	<b>3</b>	<b>1</b>	<b>3,650</b>	<b>69</b>	<b>12.5</b>	