

STATE OF NORTH CAROLINA  
SUMMARY OF QUANTITIES

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
485000000-M	1205	3,295	M	REMOVAL OF PAVEMENT MARKING LINES (100MM)	577500000-M	1525	2	EA	1200MM DIA PRECAST CONC SEWER MANHOLE 0-1.8M DEPTH	608700000-M	1660	20	HA	MOWING	740800000-M	1722	5	EA	25MM RISER WITH WEATHERHEAD
486000000-M	1205	42	M	REMOVAL OF PAVEMENT MARKING LINES (200MM)	578000000-M	1525	6	M	PRECAST CONC MANHOLE WALL, ***MM DIA, OVER 1.8M HT (1200MM)	609000000-M	1661	450	KG	SEED FOR REPAIR SEEDING	742000000-M	1722	6	EA	50MM RISER WITH WEATHERHEAD
487000000-M	1205	28	M	REMOVAL OF PAVEMENT MARKING LINES (600MM)	580400000-M	1530	120	M	FILL OR REMOVE ABANDONED 300MM PIPE, ***** (CONC SEWER )	609300000-M	1661	1.5	MTN	FERTILIZER FOR REPAIR SEEDING	743200000-M	1722	4	EA	50MM RISER WITH HEAT SHRINK TUBING
487500000-N	1205	12	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	580400000-M	1530	168	M	FILL OR REMOVE ABANDONED 300MM PIPE, ***** (DI WATER PIPE)	609600000-M	1662	1,625	KG	SEED FOR SUPPLEMENTAL SEEDING	744400000-M	1725	3,114	M	INDUCTIVE LOOP SAWCUT
490500000-N	1253	1,103	EA	SNOWPLOWABLE RAISED PAVEMENT MARKERS	581600000-N	1530	1	EA	BREAK DOWN, PLUG, & FILL ABANDONED UTILITY MANHOLE	610800000-M	1665	96.75	MTN	FERTILIZER TOPDRESSING	745600000-M	1726	7,875	M	LEAD-IN CABLE
491500000-M	1264	15	EA	2.1M U-CHANNEL POSTS	582200000-N	1530	1	EA	BREAK DOWN & REBUILD EXISTING MANHOLE	610900000-M	SP	0.7	HA	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLUEGRASS)	751600000-M	1730	1,951	M	COMMUNICATIONS CABLE (**FIBER) (12)
495500000-N	1264	15	EA	OBJECT MARKERS (END OF ROAD)	588200000-N	SP	3	EA	GENERIC UTILITY ITEM RELOCATE EXISTING 50MM WATER METER	611100000-M	SP	100	M	IMPERVIOUS DIKE	755200000-N	1731	2	EA	INTERCONNECT CENTER
525500000-N	1413	Lump Sum		PORTABLE LIGHTING	600600000-M	1605	6,130	M	TEMPORARY SILT FENCE	611400000-N	SP	36.5	HR	SPECIALIZED HAND MOWING	756400000-N	1732	2	EA	FIBER-OPTIC TRANSCEIVER
526500000-M	SP	20	M	GENERIC LIGHTING ITEM ELECTRICAL UNDERGROUND CONDUIT (100 MM, METALLIC)	600600000-M	1610	920	MTN	STONE FOR EROSION CONTROL, CLASS A	611700000-N	1675	24	EA	RESPONSE FOR EROSION CONTROL	756600000-N	1733	9	EA	DELINEATOR MARKER
530000000-M	1505	110	MTN	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	600900000-M	1610	17,200	MTN	STONE FOR EROSION CONTROL, CLASS B	611800000-N	SP	18	EA	ROOTWADS	756800000-N	SP	1	EA	FURNISH FIBER-OPTIC RESTORATION KIT
530600000-M	SP	110	MTN	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	601200000-M	1610	6,680	MTN	SEDIMENT CONTROL STONE	612000000-M	SP	630	M3	CULVERT DIVERSION CHANNEL	757400000-N	SP	1	EA	FURNISH FIBER-OPTIC TRANSCEIVER
536000000-M	1510	32	M	150MM DI WATER PIPE, PC 2.41MPA	601500000-M	1615	38	HA	TEMPORARY MULCHING	612300000-M	1670	5	HA	REFORESTATION	757600000-N	1740	20	EA	METAL STRAIN SIGNAL POLE
537800000-M	1510	328	M	300MM DI WATER PIPE, PC 2.41MPA	601800000-M	1620	2,425	KG	SEED FOR TEMPORARY SEEDING	612600000-M	SP	0.12	HA	STREAMBANK REFORESTATION	761300000-N	SP	20	EA	SOIL TEST
540800000-M	1510	21	M	***MM COPPER WATER PIPE, TYPE K (50MM)	602100000-M	1620	19.5	MTN	FERTILIZER FOR TEMPORARY SEEDING	706000000-M	1705	1,706	M	SIGNAL CABLE	761400000-M	SP	92	M	DRILLED PIER FOUNDATION (***MM DIA) (1067MM)
541400000-M	1510	16	M	20MM COPPER WATER PIPE, TYPE K	602400000-M	1622	1,100	M	TEMPORARY SLOPE DRAINS	712000000-M	1705	51	EA	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	761400000-M	SP	92	M	DRILLED PIER FOUNDATION (***MM DIA) (1067MM)
548000000-M	1510	768	KG	DUCTILE IRON WATER PIPE FITTINGS, 1.72MPA MIN WP	602700000-N	1622	55	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	713200000-M	1705	1	EA	VEHICLE SIGNAL HEAD (300MM, 4 SECTION)	763600000-N	1745	4	EA	SIGN FOR SIGNALS
554000000-M	1510	1	EA	150MM GATE VALVE & VALVE BOX, 1.38MPA WP	603000000-M	1630	69,515	M3	SILT EXCAVATION	714400000-M	1705	8	EA	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)	767500000-N	SP	2	EA	LED BLANKOUT SIGN
555800000-M	1510	2	EA	300MM GATE VALVE & VALVE BOX, ***MPA WP (1.38MPA)	603600000-M	1631	21,400	M2	MATTING FOR EROSION CONTROL	725200000-M	1710	1,138	M	MESSENGER CABLE (6.35MM)	768400000-N	1750	4	EA	SIGNAL CABINET FOUNDATION
564800000-N	1510	13	EA	RELOCATE EXISTING WATER METER (20MM)	603700000-M	SP	210	M2	COIR FIBER MAT	726400000-M	1710	901	M	MESSENGER CABLE (9.52MM)	782800000-N	1751	4	EA	CONTROLLER WITH CABINET (NEMA TS-2, TYPE 2 CONTROLLER, TYPE 1 CABINET, BASE MOUNTED)
567200000-N	1510	4	EA	RELOCATE EXISTING FIRE HYDRANT	603800000-M	SP	970	M2	PERMANENT SOIL REINFORCEMENT MAT	728800000-M	1715	25	M	TRENCHING (PAVED)	784000000-N	1751	1	EA	CONTROLLER WITH CABINET (NEMA TS-2, TYPE 2 CONTROLLER, TYPE 1 CABINET, POLE MOUNTED)
573800000-M	1520	113	M	300MM DI SEWER PIPE, PC 2.41MPA	604200000-M	1632	920	M	6.4MM HARDWARE CLOTH	730000000-M	1715	2,511	M	TRENCHING (UNPAVED)	785200000-N	SP	29	EA	DETECTOR CARD (NEMA TS-2)
					606900000-M	1638	300	M3	STILLING BASINS	730200000-M	SP	169	M	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, 31.75MM (** CONDUIT) (1)	794800000-N	SP	1	EA	TRAFFIC SIGNAL REMOVAL
					608400000-M	1660	57.5	HA	SEEDING & MULCHING	732400000-N	1716	47	EA	JUNCTION BOX (STANDARD SIZE)					
										733600000-N	1716	12	EA	JUNCTION BOX (OVER-SIZED)					
										736000000-N	1720	7	EA	WOOD POLE					
										737200000-N	1721	18	EA	GUY ASSEMBLY					