

PROJECT NAME US 70
 PROJECT NUMBER R-2911A

COMPUTED BY BDS
 CHECKED BY SLS

DATE January 29, 2004
 SHEET 2 OF 3

STATION	STATION	TOTAL EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT EXCAV.	UNSUIT. EXCAV.	SUITABLE EXCAV.	TOTAL EMB.	ROCK EMB.	EARTH EMB.	EMB. + 20%	BORROW	SUITABLE WASTE	UNSUIT. WASTE	TOTAL WASTE
SUMMARY #6														
-L-														
50+00	60+00	219648				219648	157524		157524	189029	0	30619		30619
-Y9-														
10+10	11+10	7093				7093	46		46	55	0	7038		7038
-DET2-														
10+30	10+80	15798				15798	0		0	0	0	15798		15798
TOTAL SUMMARY #6		242539				242539	157570		157570	189083	0	53455		53455
SUMMARY #7														
-L-														
60+00	70+00	102414				102414	61192		61192	73430	0	28984		28984
-Y10-														
10+64	12+76	1479				1479	175		175	210	0	1269		1269
TOTAL SUMMARY #7		103893				103893	61367		61367	73640	0	30253		30253
SUMMARY #8														
-L-														
70+00	80+00	6328				6328	60366		60366	72439	66111	0		0
-Y11-														
10+40	12+15	208				208	545		545	655	447	0		0
-DET3-														
10+06	11+15	143				143	78		78	94	0	49		49
-Y12-														
10+12	11+89	333				333	1536		1536	1843	1510	0		0
TOTAL SUMMARY #8		7012				7012	62525		62525	75030	68068	49		49
SUMMARY #9														
-L-														
80+00	90+36	21575				21575	16299		16299	19559	0	2016		2016
-Y13-														
09+65	10+39	179				179	217		217	260	81	0		0
TOTAL SUMMARY #9		21755				21755	16516		16516	19819	81	2016		2016