PROJECT REFERENCE NO.	SHEET NO.
U-2734	6
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

METRIC

5 0 10

CONST.REV. _____

R/W REV. _____

INCOMPLETE PLANS
DO NOT USE FOR R/W ACQUISITION

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT
IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY
NCGS FOR MONUMENT "SUNOCO"
WITH NAD 83 STATE PLANE GRID COORDINATES OF
NORTHING: 67788.587(m) EASTING: 717730.854(m)
THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT
(GROUND TO GRID) IS: 1.000017450
THE N.C. LAMBERT GRID BEARING
LOCALIZED HORIZONTAL GROUND DISTANCE FROM
"SUNOCO" TO -L- STATION 13+10.000 IS
S 3° 43' 57.370" W 3,681.050m
ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES
VERTICAL DATUM USED IS NGVD 29

-L- STA.13+10.000 BEGIN STATE PROJECT U-2734
-L- STA.13+10.000 BEGIN F.A.PROJECT NHF-1409 (3)

NAD 83

BL-68 PINC 6+94.002
-L- STA. 13+29.255
19.186 (LT)

BL-70 PINC 9+34.894
-L- STA. 15+70.128
11.423 (LT)

230m TAPER

MEDIAN OPENING FOR SOUTHBOUND "EMERGENCY TRAFFIC

SR 1409 MILITARY CUTOFF RD

N 5° 21' 47.2" E

N 4° 14' 14.7" E

N 5° 29' 49.4" E

N 4° 28' 19.0" E

TIE TO EXIST. C&G

OBLITERATE AND REMOVE

BEGIN -BIKEPATH-
-L- STA.13+20 +/-

I S M BUS

3 - ISL'S
3 FUEL PUMPS
U/MTL CANOPY

U/G FUEL TANKS
3 - 37,850L
1 - 18,930L

I S BK BUS

CONC DOCK

FLAGSTAFF

CONC PARKING

140m CONC ENTRANCE

UNDER CONSTRUCTION

DETENSION BASIN

approx.location of fence

LEGEND

PAVEMENT REMOVAL

PROPOSED BIKE PATH

PROPOSED 125mm CONCRETE MONOLITHIC ISLAND (SURFACE MOUNTED)