

STATE OF NORTH CAROLINA SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200757

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+89.75)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	200	CY	UNDERCUT EXCAVATION
0318000000-E	300	12	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0366000000-E	310	110	LF	15" RC PIPE CULVERTS, CLASS III
1220000000-E	545	50	TON	INCIDENTAL STONE BASE
1489000000-E	610	310	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	240	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	580	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	63	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2286000000-N	840	3	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	360	LF	SHOULDER BERM GUTTER
3030000000-E	862	600	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3656000000-E	876	150	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	2	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4400000000-E	1110	320	SF	WORK ZONE SIGNS (STATIONARY)
4410000000-E	1110	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	4	EA	WARNING FLAG SETS
4430000000-N	1130	50	EA	DRUMS

ItemNumber	Sec #	Quantity	Unit	Description
4445000000-E	1145	44	LF	BARRICADES (TYPE III)
4810000000-E	1205	8,840	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	14	EA	PERMANENT RAISED PAVEMENT MARKERS
5300000000-E	1505	2	TON	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (V)
5306000000-E	SP	2	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (V)
5360000000-E	1510	32	LF	6" DI WATER PIPE, PC 350
5414000000-E	1510	36	LF	3/4" COPPER WATER PIPE, TYPE K
5480000000-E	1510	150	LB	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP
5540000000-E	1510	2	EA	6" GATE VALVE & VALVE BOX, 200# WP
5648000000-N	1510	1	EA	RELOCATE EXISTING WATER METER
5666000000-E	1510	1	EA	FIRE HYDRANT, ***** WP (150# WP)
6000000000-E	1605	570	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	120	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	165	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	2	ACR	TEMPORARY MULCHING
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
6024000000-E	1622	50	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6030000000-E	1630	35	CY	SILT EXCAVATION
6033000000-E	1631	420	SY	SYNTHETIC ROVING
6036000000-E	1631	700	SY	MATting FOR EROSION CONTROL
6042000000-E	1632	500	LF	1/4" HARDWARE CLOTH
6048000000-E	SP	100	SY	FLOATING TURBIDITY CURTAIN
6084000000-E	1660	2	ACR	SEEDING & MULCHING

ItemNumber	Sec #	Quantity	Unit	Description
6087000000-E	1660	1.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1.5	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL