



| | |
|---------------------|-----------|
| PROJ. REFERENCE NO. | SHEET NO. |
| B-1019 | PM-1 |

Pavement Marking Schedule
TIP Project # B-1019

| SYMBOL | DESCRIPTION | PAY ITEM | QUANTITY | BREAKDOWN | TOTAL QUANTITY |
|--|----------------------|------------------------------|----------|-----------|----------------|
| FINAL PAVEMENT MARKINGS | | | | | |
| | | THERMOPLASTIC (100MM, 2.3MM) | | | |
| TA | WHITE EDGELINE | | 1157 | M | |
| | | | | | TOTAL 1157 M |
| | | THERMOPLASTIC (100MM, 3.1MM) | | | |
| TC | 3 M. WHITE SKIP | | 8 | M | |
| TI | YELLOW DOUBLE CENTER | | 2314 | M | |
| | | | | | TOTAL 2322 M |
| | | THERMOPLASTIC (200MM, 2.3MM) | | | |
| TT | YELLOW DIAGONAL | | 73 | M | |
| | | | | | TOTAL 73 M |
| | | THERMOPLASTIC (600MM, 3.1MM) | | | |
| T2 | WHITE STOPBAR | | 18 | M | |
| | | | | | TOTAL 18 M |
| THERMOPLASTIC PAVEMENT MARKING SYMBOLS (2.3MM) | | | | | |
| UA | LEFT TURN ARROW | | 1 | EA | |
| UC | STRAIGHT ARROW | | 5 | EA | |
| UE | COMBO.STRAIGHT/RIGHT | | 1 | EA | |
| | | | | | TOTAL 7 EA |
| MARKERS | | | | | |
| PERMANENT RAISED PAVEMENT MARKERS | | | | | |
| MA | YELLOW & YELLOW | | 80 | EA | |
| | | | | | TOTAL 80 EA |

30-JUN-2004 10:55
 H:\TCP\B1019\10-TIP\01.dwg
 mmorley AT ETC8887

| | | |
|---------------------------------------|--|--|
| APPROVED: <i>J. Kus</i> DATE: 6/30/04 | FINAL PAVEMENT MARKING SCHEDULE | |
| | SCALE: NONE | |
| | DATE: 3/2004 | |
| | DWG. BY: MLM | |
| | DESIGN BY: MLM | |
| REVIEWED BY: JDK | REVISIONS | |
| | | |
| | | |
| | | |