COMPUTED BY: JLB DATE: 04 14 03

CHECKED

PROJECT REFERENCE NO.	SHEET NO.
B-4010	3

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200892

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ********** (20+93.60)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
0057000000-E	226	300	CY	UNDERCUT EXCAVATION
0080000000-E	SP	500	TON	CLASS IV SUBGRADE STABILIZATION
0134000000-E	240	500	CY	DRAINAGE DITCH EXCAVATION
0195000000-E	265	300	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	1,000	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	155	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0343000000-E	310	20	LF	15" SIDE DRAIN PIPE
0345000000-E	310	16	LF	24" SIDE DRAIN PIPE
0360000000-E	310	236	LF	12" RC PIPE CULVERTS, CLASS III
0366000000-E	310	344	LF	15" RC PIPE CULVERTS, CLASS III
0378000000-E	310	296	LF	24" RC PIPE CULVERTS, CLASS III
0384000000-E	310	136	LF	30" RC PIPE CULVERTS, CLASS III
0582000000-E	310	112	LF	15" CS PIPE CULVERTS, 0.064" THICK
0708000000-E	310	304	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	6	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0986000000-E	SP	40	LF	GENERIC PIPE ITEM 30" RCP, CLASS IV (BY BORING AND JACKING)
0995000000-E	340	38	LF	PIPE REMOVAL
1220000000-E	545	100	TON	INCIDENTAL STONE BASE
1489000000-E	610	1,300	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	800	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	900	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	150	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	50	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	9	EA	RIGHT OF WAY MARKERS
2022000000-E	815	115	CY	SUBDRAIN EXCAVATION
2033000000-E	815	85	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE
2055000000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
2220000000-E	838	4.1	CY	REINFORCED ENDWALLS
2264000000-E	840	0.36	CY	PIPE PLUGS
2286000000-N	840	11	EA	MASONRY DRAINAGE STRUCTURES
2366000000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.24
2367000000-N	840	8	EA	FRAME WITH TWO GRATES, STD 840.29
2462000000-E	SP	2	EA	*" SLUICE GATE (22")
2474000000-N	SP	Lump Sum		GENERIC DRAINAGE ITEM HAZARDOUS SPILL BASIN
2556000000-E	846	950	LF	SHOULDER BERM GUTTER
2577000000-E	846	300	LF	CONCRETE EXPRESSWAY GUTTER
3030000000-E	862	1,175	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3649000000-E	876	125	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	1,000	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	2	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4400000000-E	1110	169	SF	WORK ZONE SIGNS (STATIONARY)
4405000000-E	1110	96	SF	WORK ZONE SIGNS (PORTABLE)
4430000000-N	1130	39	EA	DRUMS
4435000000-N	1135	39	EA	CONES
4455000000-N	1150	60	MD	FLAGGER
4465000000-N	1160	2	EA	TEMPORARY CRASH CUSHIONS
4480000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)
4485000000-E	1170	300	LF	PORTABLE CONCRETE BARRIER
4650000000-N	1251	49	EA	TEMPORARY RAISED PAVEMENT MARKERS
4730000000-E	1205	7,800	LF	EPOXY PAVEMENT MARKING LINES (4")
4810000000-E	1205	15,600	LF	PAINT PAVEMENT MARKING LINES (4")
4850000000-E	1205	300	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
4900000000-N	1252	4	EA	PERMANENT RAISED PAVEMENT MARKERS
4905000000-N	1253	20	EA	SNOWPLOWABLE RAISED PAVEMENT MARKERS
6000000000-E	1605	1,425	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	430	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	450	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	7	ACR	TEMPORARY MULCHING
6018000000-E	1620	250	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	1	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	75	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6030000000-E	1630	1,445	CY	SILT EXCAVATION
6036000000-E	1631	2,000	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	200	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	12	EA	SPECIAL STILLING BASINS
6084000000-E	1660	9	ACR	SEEDING & MULCHING
6087000000-E	1660	4	ACR	MOWING
6090000000-E	1661	100	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	175	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	6.5	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

01/28/04
r:\roadway\proj\b4010_rdy_sum.dgn