

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200828

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+37.50)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	500	CY	UNDERCUT EXCAVATION
0134000000-E	240	200	CY	DRAINAGE DITCH EXCAVATION
0195000000-E	265	2,000	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	2,000	SY	FABRIC FOR SOIL STABILIZATION
0199000000-E	SP	200	SF	TEMPORARY SHORING
0318000000-E	300	18	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0343000000-E	310	24	LF	15" SIDE DRAIN PIPE
0366000000-E	310	36	LF	15" RC PIPE CULVERTS, CLASS III
0582000000-E	310	64	LF	15" CS PIPE CULVERTS, 0.064" THICK
0588000000-E	310	44	LF	18" CS PIPE CULVERTS, 0.064" THICK
0636000000-E	310	2	EA	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")
0995000000-E	340	86	LF	PIPE REMOVAL
1121000000-E	520	72	TON	AGGREGATE BASE COURSE
1220000000-E	545	100	TON	INCIDENTAL STONE BASE
1489000000-E	610	1,210	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	610	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	680	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	125	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2286000000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES

ItemNumber	Sec #	Quantity	Unit	Description
2367000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	70	LF	SHOULDER BERM GUTTER
3030000000-E	862	387.5	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3566000000-E	867	250	LF	WOVEN WIRE FENCE RESET
3569000000-E	867	340	LF	BARBED WIRE FENCE RESET
3649000000-E	876	220	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	760	SY	FILTER FABRIC FOR DRAINAGE
4400000000-E	1110	52	SF	WORK ZONE SIGNS (STATIONARY)
4405000000-E	1110	96	SF	WORK ZONE SIGNS (PORTABLE)
4410000000-E	1110	50	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	20	EA	DRUMS
4435000000-N	1135	40	EA	CONES
4445000000-E	1145	50	LF	BARRICADES (TYPE III)
4450000000-N	1150	256	HR	FLAGGER
4465000000-N	1160	3	EA	TEMPORARY CRASH CUSHIONS
4485000000-E	1170	370	LF	PORTABLE CONCRETE BARRIER
4650000000-N	1251	94	EA	TEMPORARY RAISED PAVEMENT MARKERS
4685000000-E	1205	2,810	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4686000000-E	1205	2,810	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4810000000-E	1205	29,712	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	36	EA	PERMANENT RAISED PAVEMENT MARKERS
5300000000-E	1505	230	TON	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (VI)

ItemNumber	Sec #	Quantity	Unit	Description
5306000000-E	SP	230	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)
5360000000-E	1510	100	LF	6" DI WATER PIPE, PC 350
5384000000-E	1510	864	LF	16" DI WATER PIPE, PC ***** (PC 350)
5480000000-E	1510	2,025	LB	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP
5594000000-E	SP	1	EA	*** AIR RELEASE VALVE & MAN- HOLE (2")
5672000000-N	1510	1	EA	RELOCATE EXISTING FIRE HYDRANT
5756000000-E	1520	440	LB	DUCTILE IRON SEWER PIPE FIT- TINGS, ***** (PC 350)
5798000000-E	1530	290	LF	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", PVC C-90 DR 18)
5810000000-E	1530	856	LF	FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI WATER PIPE)
5882000000-N	SP	2	EA	GENERIC UTILITY ITEM 6" RESTRAINED RETAINER GLAND
5888000000-E	SP	292	LF	GENERIC UTILITY ITEM 8" DI FORCE MAIN SEWER PIPE, CL 50
6000000000-E	1605	1,795	LF	TEMPORARY SILT FENCE
6006000000-E	1610	60	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	380	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	120	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	5	ACR	TEMPORARY MULCHING
6018000000-E	1620	200	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEED- ING
6024000000-E	1622	175	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6030000000-E	1630	575	CY	SILT EXCAVATION
6033000000-E	1631	518	SY	SYNTHETIC ROVING
6036000000-E	1631	830	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	40	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	6.5	ACR	SEEDING & MULCHING
6087000000-E	1660	3	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	125	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	5	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	2	EA	RESPONSE FOR EROSION CONTROL
6123000000-E	1670	0.25	ACR	REFORESTATION