

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26+65.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,000 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	14,200 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	219 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	200 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	60 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0014	0345000000-E	310	24" SIDE DRAIN PIPE	36 LF		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	132 LF		
0016	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	60 LF		
0017	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (96", 0.168")	168 LF		
0018	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	96 LF		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0995000000-E	340	PIPE REMOVAL	228 LF		
0020	1121000000-E	520	AGGREGATE BASE COURSE	1,100 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0022	1275000000-E	600	PRIME COAT	1,070 GAL		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	750 TON		
0024	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	900 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	91 TON		
0026	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0027	2000000000-N	806	RIGHT OF WAY MARKERS	25 EA		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	10 EA		
0030	2486000000-E	SP	GENERIC DRAINAGE ITEM SANDBAG HEADWALL	1,000 SF		
0031	2556000000-E	846	SHOULDER BERM GUTTER	2,350 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	2,375 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0036	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,525 LF		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0038	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	13 EA		
0039	3628000000-E	876	PLAIN RIP RAP, CLASS I	200 TON		
0040	3649000000-E	876	PLAIN RIP RAP, CLASS B	6 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,627 SY		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	276 SF		
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	224 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	72 SF		
0045	4430000000-N	1130	DRUMS	50 EA		
0046	4435000000-N	1135	CONES	50 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0048	4455000000-N	1150	FLAGGER	50 MD		
0049	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	1 EA		
0050	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	216 EA		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	51,600 LF		
0052	6000000000-E	1605	TEMPORARY SILT FENCE	1,660 LF		
0053	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	200 TON		
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,020 TON		
0055	6012000000-E	1610	SEDIMENT CONTROL STONE	850 TON		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6015000000-E	1615	TEMPORARY MULCHING	6.5 ACR		
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0058	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0059	6024000000-E	1622	TEMPORARY SLOPE DRAINS	40 LF		
0060	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0061	6030000000-E	1630	SILT EXCAVATION	2,455 CY		
0062	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,820 SY		
0063	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	25 SY		
0064	6042000000-E	1632	1/4" HARDWARE CLOTH	200 LF		
0065	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	100 SY		
0066	6069000000-E	1638	STILLING BASINS	40 CY		
0067	6070000000-N	SP	SPECIAL STILLING BASINS	16 EA		
0068	6084000000-E	1660	SEEDING & MULCHING	7 ACR		
0069	6087000000-E	1660	MOWING	4 ACR		
0070	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150 LB		
0073	6108000000-E	1665	FERTILIZER TOPDRESSING	5.25 TON		
0074	6111000000-E	SP	IMPERVIOUS DIKE	150 LF		
0075	6114000000-N	SP	SPECIALIZED HAND MOWING	6 HR		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	16 EA		
0077	6120000000-E	SP	CULVERT DIVERSION CHANNEL	80 CY		
0078	6123000000-E	1670	REFORESTATION	1.5 ACR		

CULVERT ITEMS

0079	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+91.00 -L-)	Lump Sum	L.S.	
0080	8126000000-N	414	CULVERT EXCAVATION, STA ***** (15+91.00 -L-)	Lump Sum	L.S.	
0081	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	138 TON		
0082	8196000000-E	420	CLASS A CONCRETE (CULVERT)	195.9 CY		
0083	8245000000-E	425	REINFORCING STEEL (CULVERT)	39,883 LB		

STRUCTURE ITEMS

0084	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (26+65.00 -L-)	Lump Sum	L.S.	
0085	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (26+65.00 -L-)	Lump Sum	L.S.	
0086	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26+65.00 -L-)	Lump Sum	L.S.	
0087	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SOIL	177.5 LF		
0088	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	97 LF		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	155.9 LF		
0090	8113000000-N	SP	SID INSPECTION	2 EA		
0091	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0092	8116000000-E	SP	CSL TUBES	1,176.6 LF		
0093	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (26+65.00 -L-)	Lump Sum	L.S.	
0094	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	105.8 CY		
0095	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26+65.00 -L-)	Lump Sum	L.S.	
0096	8217000000-E	425	REINFORCING STEEL (BRIDGE)	40,605 LB		
0097	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,704 LB		
0098	8364000000-E	450	HP12X53 STEEL PILES	360 LF		
0099	8503000000-E	460	CONCRETE BARRIER RAIL	435.5 LF		
0100	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	390 TON		
0101	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	433 SY		
0102	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0103	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,389.75 LF		

0728/Aug11/Q185629.45/D475081940000/E103

Total Amount Of Bid For Entire Project :

C200961
CASWELL COUNTY

2/16/99

Contract No: C200961

Counties: Caswell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General