



PROJ. REFERENCE NO. R-2610A	SHEET NO. PM-1
--------------------------------	-------------------

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM/QUANTITY BREAKDOWN	TOTAL QUANTITY
<u>PAVEMENT MARKING LINES</u>			
<u>THERMOPLASTIC (100mm, 2.3mm)</u>			
TA	WHITE EDGELINE	16,554 m	
TB	YELLOW EDGELINE	15,032 m	
			TOTAL 31,586 m
<u>THERMOPLASTIC (100mm, 3.1mm)</u>			
TC	3M WHITE SKIP	3477 m	
TD	0.5M WHITE MINISKIP	247 m	
TE	WHITE SOLID LANE LINE	90 m	
TI	YELLOW DOUBLE CENTER LINE	1722 m	
			TOTAL 5536 m
<u>THERMOPLASTIC (200mm, 2.3mm)</u>			
TP	WHITE GORE	2644 m	
TQ	WHITE DIAGONAL	212 m	
			TOTAL 2856 m
<u>THERMOPLASTIC (100mm, 6.2mm)</u>			
T2	WHITE STOP BAR	116 m	
			TOTAL 116 m
<u>THERMOPLASTIC SYMBOLS (2.3mm)</u>			
UA	LEFT TURN ARROW	36 EA	
UB	RIGHT TURN ARROW	2 EA	
UC	STRAIGHT ARROW	44 EA	
			TOTAL 82 EA
<u>THERMOPLASTIC THICK CHARACTER (120mm, 3.1mm)</u>			
UI	ALPHANUMERIC CHARACTER	4 EA	
			TOTAL 4 EA
<u>SNOWPLOWABLE PAVEMENT MARKERS</u>			
ME	YELLOW AND YELLOW	11 EA	
MF	CRYSTAL AND RED	1268 EA	
			TOTAL 1279 EA

22-MAR-2004 15:57
 D:\CPY-2610a-pm_base01.dwg
 DERICHARDSON A1 TELC206432

APPROVED: <i>MJM</i>	DATE: 3/26/04	FINAL PAV'T MARKING SCHEDULE							
	SCALE: NONE								
	DATE: 03/03								
	DWG. BY: DER								
	DESIGN BY:								
REVIEWED BY:		<table border="1"> <tr> <th colspan="2">REVISIONS</th> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> </table>		REVISIONS					
REVISIONS									
<small>CADD FILE R2610A_PM_BASE01.DGN</small>									