

3E/40

EARTHWORK SUMMARIES

Volumes in Cubic Meters

PROJECT R-2610A

COUNTY Chatham

DATE: REV. 2/20/03

SHEET 3 OF 5 SHEETS

RD10S01C

LINE	STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE		
			TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. 15%		ROCK	SUITABLE	UNSUIT.
-L- LT	74+40	85+79.544	10,041	0	0	0	10,041	6,949	0	6,949	7,991	0	0	2,050	0
-LPD- RT	10+09.152	12+56.898	298	0	0	0	298	479	0	479	551	253	0	0	0
-LPD- LT	10+60	11+80	188	0	0	0	188	4	0	4	5	0	0	183	0
		SUBTOTAL	10,527	0	0	0	10,527	7,432	0	7,432	8,547	253	0	2,233	0
-L- RT	12+20	17+40	88	0	0	0	88	9,238	0	9,238	10,624	10,536	0	0	0
-Y1- RT	10+60	10+80	23	0	0	0	23	57	0	57	66	43	0	0	0
		SUBTOTAL	111	0	0	0	111	9,295	0	9,295	10,690	10,579	0	0	0
-L- RT	18+80	21+20	269	0	0	0	269	1,408	0	1,408	1,619	1,350	0	0	0
-Y3REV-LT	10+40	10+80	170	0	0	0	170	0	0	0	0	0	0	170	0
		SUBTOTAL	439	0	0	0	439	1,408	0	1,408	1,619	1,350	0	170	0
-L- RT	23+40	26+80	1,131	0	0	0	1,131	1,451	0	1,451	1,669	538	0	0	0
-Y4- LT	10+80	11+20	42	0	0	0	42	68	0	68	78	36	0	0	0
-Y4- RT	10+80	11+20	184	0	0	0	184	28	0	28	32	0	0	152	0
		SUBTOTAL	1,357	0	0	0	1,357	1,547	0	1,547	1,779	574	0	152	0
SHEET	TOTAL		12,434	0	0	0	12,434	19,682	0	19,682	22,635	12,756	0	2,555	0