

3D/40

EARTHWORK SUMMARIES

Volumes in Cubic Meters

PROJECT R-2610A

COUNTY Chatham

DATE: REV. 2/20/03

SHEET 2 OF 5 SHEETS

RD10S01C

LINE	STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE		
			TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. 15%		ROCK	SUITABLE	UNSUIT.
-L- LT	38+60	46+00	5,393	0	0	0	5,393	7,827	0	7,827	9,001	3,608	0	0	0
-Y7- LT	10+20	11+20	456	0	0	0	456	48	0	48	55	0	0	401	0
-Y7- RT	10+20	11+20	133	0	0	0	133	0	0	0	0	0	0	133	0
		SUBTOTAL	5,982	0	0	0	5,982	7,875	0	7,875	9,056	3,608	0	534	0
-L- LT	46+00	55+00	10,748	0	0	0	10,748	12,890	0	12,890	14,824	4,076	0	0	0
-L- LT	55+00	62+40	36,901	0	0	0	36,901	7,065	0	7,065	8,125	0	0	28,776	0
-L- LT	62+40	71+20	7,454	0	0	0	7,454	9,369	0	9,369	10,774	3,320	0	0	0
-L- LT	71+20	74+40	1,444	0	0	0	1,444	392	0	392	451	0	0	993	0
-RPD- FULL	11+39.267	12+40	1,809	0	0	0	1,809	284	0	284	327	0	0	1,482	0
-RPD- LT	12+40	13+43.281	1,889	0	0	0	1,889	0	0	0	0	0	0	1,889	0
-RPD- RT	12+40	13+43.281	351	0	0	0	351	0	0	0	0	0	0	351	0
		SUBTOTAL	5,493	0	0	0	5,493	676	0	676	778	0	0	4,715	0
SHEET TOTAL			66,578	0	0	0	66,578	37,875	0	37,875	43,557	11,004	0	34,025	0