R:\Roadway\Xsc\EARTHWORK\U0620_RDY_EW_L1L.LOG

PROJ. REFERENCE NO.	SHEET NO.
U-0620	X-E

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y3		
15+50.00	79	587
15+80.00	196	419
16+00.00	240	253
16+50.00	888	1131

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y4		
10+50.00	0	0
11+00.00	163	10
11+50.00	229	0
12+00.00	127	4
12+50.00	31	4
13+00.00	0	1
13+50.00	0	1
14+00.00	0	0
14+24.00	0	0

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y5		
10+50.00	0	0
11+00.00	7	65
11+50.00	14	13

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y6		
10+50.00	0	0
11+00.00	0	167
11+50.00	2	91
12+00.00	12	50

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y7		
11+00.00	0	0
11+50.00	43	10
12+00.00	46	6

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y8		
15+50.00	0	0
16+00.00	35	291
16+50.00	30	179
17+00.00	14	875
17+50.00	11	1515
18+00.00	10	995
18+50.00	0	452
19+00.00	49	372
19+50.00	97	413

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y9		
12+00.00	0	0
12+50.00	6	64
13+00.00	4	45

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y10		
12+00.00	0	0
12+50.00	57	10
13+00.00	96	4

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y11		
12+50.00	0	0
13+00.00	0	1
13+50.00	0	1
14+00.00	0	1
14+50.00	0	1

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y12		
13+00.00	0	0
13+50.00	23	234
14+00.00	20	207
14+50.00	23	110
15+00.00	44	40
15+50.00	114	12
16+00.00	221	1
16+50.00	388	0
17+00.00	579	0
17+50.00	660	0
18+00.00	620	0
18+50.00	574	2
19+00.00	576	5
19+50.00	633	4
20+00.00	807	1
20+50.00	709	1
22+00.00	1292	168
22+50.00	800	84
23+00.00	935	45
23+50.00	595	32
24+00.00	470	25
24+50.00	349	11
25+00.00	261	8
25+50.00	140	64
26+00.00	66	102
26+50.00	64	86
27+00.00	45	126
27+50.00	26	171
28+00.00	25	207
28+50.00	29	256

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y12		
29+00.00	18	238
29+50.00	8	202
30+00.00	9	196

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y14		
10+50.00	0	0
11+00.00	31	10
11+50.00	14	10

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Y15		
10+00.00	0	0
10+50.00	26	80
11+00.00	21	158
11+50.00	18	222
12+00.00	16	293
12+50.00	14	353
13+00.00	14	436
13+50.00	18	426
14+00.00	23	276
14+50.00	44	156
15+00.00	64	73
15+50.00	42	72
16+00.00	12	133
16+50.00	8	141
17+00.00	21	102
17+50.00	39	61
18+00.00	91	30
18+50.00	158	20
19+50.00	184	341
20+00.00	23	194
20+50.00	37	77
21+00.00	48	91
21+50.00	87	116
22+00.00	105	130
22+50.00	83	112
23+00.00	42	83
23+50.00	21	82
24+00.00	32	108
24+50.00	31	135
25+00.00	15	157
25+50.00	17	168
26+00.00	26	184
26+50.00	23	183
27+00.00	13	185
27+50.00	6	210
28+00.00	5	220
28+50.00	8	207

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Det2		
10+00.01	0	0
10+50.00	28	15
11+00.00	19	40
11+50.00	8	122
12+00.00	7	195
12+50.00	6	361
13+00.00	0	446
13+50.00	0	240
14+00.00	3	88
14+50.00	15	51
15+00.00	28	20

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
Dixie1		
10+50.00	0	0
11+00.00	2	289
11+50.00	2	544