

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

ItemNumber	Sec #	Quantity	Unit	Description
482000000-E	1205	4,354	LF	PAINT PAVEMENT MARKING LINES (8")
483500000-E	1205	644	LF	PAINT PAVEMENT MARKING LINES (24")
484000000-N	1205	16	EA	PAINT PAVEMENT MARKING CHARACTER
484500000-N	1205	42	EA	PAINT PAVEMENT MARKING SYMBOL
485000000-E	1205	15,848	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
486000000-E	1205	519	LF	REMOVAL OF PAVEMENT MARKING LINES (8")
487500000-N	1205	4	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS
490000000-N	1252	329	EA	PERMANENT RAISED PAVEMENT MARKERS
530000000-E	1505	128	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)
530600000-E	SP	128	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)
531800000-E	1505	80	TON	PAVEMENT REPAIR FOR UTILITY WORK
536000000-E	1510	48	LF	6" DI WATER PIPE, PC 350
536600000-E	1510	290	LF	8" DI WATER PIPE, PC 350
537800000-E	1510	244	LF	12" DI WATER PIPE, PC 350
539600000-E	1510	65	LF	*** DI RESTRAINED JOINT WATER PIPE, CLASS ***** (12", 50)
540200000-E	1510	1,075	LB	DI RESTRAINED JOINT WATER PIPE FITTINGS, 250# MIN WP
548000000-E	1510	2,490	LB	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP
554000000-E	1510	2	EA	6" GATE VALVE & VALVE BOX, 200# WP
567200000-N	1510	2	EA	RELOCATE EXISTING FIRE HYDRANT
572000000-E	1520	757.12	LF	*** DI SEWER PIPE, PC ***** (16", 350)
572600000-E	1520	549.06	LF	8" DI SEWER PIPE, PC 350
573200000-E	1520	383.71	LF	10" DI SEWER PIPE, PC 350
577500000-E	1525	8	EA	4' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH
577600000-E	1525	2	EA	5' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH
578000000-E	1525	72	LF	PRECAST CONC MANHOLE WALL, * DIA, OVER 6' HT (4')
578000000-E	1525	19	LF	PRECAST CONC MANHOLE WALL, * DIA, OVER 6' HT (5')
579800000-E	1530	171	LF	FILL OR REMOVE ABANDONED *** PIPE, ***** (10", DI SEWER)
580400000-E	1530	215	LF	FILL OR REMOVE ABANDONED 12" PIPE, ***** (DI WATER)
581000000-E	1530	679	LF	FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI SEWER)
581600000-N	1530	6	EA	BREAK DOWN, PLUG, & FILL ABANDONED UTILITY MANHOLE
582200000-N	1530	3	EA	BREAK DOWN & REBUILD EXISTING MANHOLE
588800000-E	SP	40	LF	GENERIC UTILITY ITEM 10" DI RESTRAINED JOINT SEWER PIPE, PC 350
588800000-E	SP	40	LF	GENERIC UTILITY ITEM 16" DI RESTRAINED JOINT SEWER PIPE, PC 350
600000000-E	1605	4,745	LF	TEMPORARY SILT FENCE
600600000-E	1610	400	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	3,845	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	1,915	TON	SEDIMENT CONTROL STONE
601500000-E	1615	4	ACR	TEMPORARY MULCHING
601800000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
602400000-E	1622	600	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	17	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS

ItemNumber	Sec #	Quantity	Unit	Description
603000000-E	1630	11,175	CY	SILT EXCAVATION
603600000-E	1631	5,775	SY	MATTING FOR EROSION CONTROL
603700000-E	SP	2,200	SY	COIR FIBER MAT
603800000-E	SP	500	SY	PERMANENT SOIL REINFORCEMENT MAT
604200000-E	1632	1,060	LF	1/4" HARDWARE CLOTH
604500000-E	SP	700	LF	*** TEMPORARY PIPE (24")
606900000-E	1638	1,020	CY	STILLING BASINS
607000000-N	SP	10	EA	SPECIAL STILLING BASINS
608400000-E	1660	31.5	ACR	SEEDING & MULCHING
608700000-E	1660	1.5	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	23.75	TON	FERTILIZER TOPDRESSING
610900000-E	SP	0.6	ACR	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLUEGRASS)
611100000-E	SP	250	LF	IMPERVIOUS DIKE
611400000-N	SP	12	HR	SPECIALIZED HAND MOWING
611700000-N	1675	16	EA	RESPONSE FOR EROSION CONTROL
612600000-E	SP	1.2	ACR	STREAMBANK REFORESTATION
613200000-N	SP	345	EA	GENERIC EROSION CONTROL ITEM NATURAL STONE, BOULDER-2000LB
613200000-N	SP	600	EA	GENERIC EROSION CONTROL ITEM NATURAL STONE, BOULDER-4000LB
614700000-E	SP	2,000	LF	GENERIC EROSION CONTROL ITEM SAFETY FENCE
706000000-E	1705	2,010	LF	SIGNAL CABLE
712000000-E	1705	22	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
714400000-E	1705	13	EA	VEHICLE SIGNAL HEAD (12", 5 SECTION)
725200000-E	1710	140	LF	MESSENGER CABLE (1/4")
726400000-E	1710	1,500	LF	MESSENGER CABLE (3/8")
727900000-E	1715	1,285	LF	TRACER WIRE
730000000-E	1715	2,620	LF	TRENCHING (UNPAVED)
732400000-N	1716	22	EA	JUNCTION BOX (STANDARD SIZE)
733600000-N	1716	7	EA	JUNCTION BOX (OVER-SIZED)
736000000-N	1720	4	EA	WOOD POLE
737200000-N	1721	8	EA	GUY ASSEMBLY
740800000-E	1722	1	EA	1" RISER WITH WEATHERHEAD
742000000-E	1722	1	EA	2" RISER WITH WEATHERHEAD
744400000-E	1725	3,270	LF	INDUCTIVE LOOP SAWCUT
745600000-E	1726	5,280	LF	LEAD-IN CABLE
748100000-N	SP	1	EA	SITE SURVEY
748120000-N	SP	4	EA	LUMINAIRE ARM FOR VIDEO SYSTEM
751600000-E	1730	1,285	LF	COMMUNICATIONS CABLE (**FIBER) (12)
755200000-N	1731	3	EA	INTERCONNECT CENTER
756400000-N	1732	3	EA	FIBER-OPTIC TRANSCEIVER
756600000-N	1733	7	EA	DELINEATOR MARKER
757600000-N	1740	12	EA	METAL STRAIN SIGNAL POLE
761300000-N	SP	12	EA	SOIL TEST
761400000-E	SP	180	LF	DRILLED PIER FOUNDATION (** DIA) (42")
768400000-N	1750	3	EA	SIGNAL CABINET FOUNDATION
768800000-N	SP	3	EA	CABINET BASE ADAPTER
775600000-N	1751	3	EA	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)
778000000-N	SP	24	EA	DETECTOR CARD (TYPE 2070L)

ItemNumber	Sec #	Quantity	Unit	Description
***** BEGIN SCHEDULE HA ***** ***** (2 ALTERNATES) *****				
7481220000-N HA1	SP	1	EA	CAMERA WITH INTERNAL LOOP EMULATOR PROCESSING UNIT
*** OR ***				
7481240000-N HA2	SP	1	EA	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT
7481260000-N HA2	SP	1	EA	EXTERNAL LOOP EMULATOR PROCESSING UNIT
***** END SCHEDULE HA *****				

5/28/99

I:\AUG-2004\2-36\4256\_rdy\_typ.dgn  
UNLOADING...  
D:\DSD\2149