

6/2/99

PROJECT REFERENCE NO.		SHEET NO.	
B-4139		3	
ROADWAY DESIGN ENGINEER		PAVEMENT DESIGN ENGINEER	

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200849														
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6012000000-E	1610	40	TON	SEDIMENT CONTROL STONE
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	3360000000-E	863	687.5	LF	REMOVE EXISTING GUARDRAIL	6015000000-E	1615	0.5	ACR	TEMPORARY MULCHING
0008000000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	3649000000-E	876	2	TON	PLAIN RIP RAP, CLASS B	6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
0022000000-E	225	3,700	CY	UNCLASSIFIED EXCAVATION	3656000000-E	876	232	SY	FILTER FABRIC FOR DRAINAGE	6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL STATION ***** (17+68)	4025000000-E	901	20	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	6024000000-E	1622	50	LF	TEMPORARY SLOPE DRAINS
0057000000-E	226	500	CY	UNDERCUT EXCAVATION	4025000000-E	901	23.25	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
0063000000-N	SP	Lump Sum		GRADING	4025000000-E	901	23.25	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6030000000-E	1630	10	CY	SILT EXCAVATION
0134000000-E	240	12	CY	DRAINAGE DITCH EXCAVATION	4072000000-E	903	135	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	6036000000-E	1631	1,205	SY	MATTING FOR EROSION CONTROL
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL	4096000000-N	904	3	EA	SIGN ERECTION, TYPE D	6042000000-E	1632	40	LF	1/4" HARDWARE CLOTH
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION	4102000000-N	904	5	EA	SIGN ERECTION, TYPE E	6084000000-E	1660	0.5	ACR	SEEDING & MULCHING
0199000000-E	SP	300	SF	TEMPORARY SHORING	4155000000-N	907	9	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6087000000-E	1660	0.5	ACR	MOWING
0366000000-E	310	28	LF	15" RC PIPE CULVERTS, CLASS III	4158000000-N	907	1	EA	DISPOSAL OF SIGN SYSTEM, WOOD	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
0708000000-E	310	24	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4400000000-E	1110	110	SF	WORK ZONE SIGNS (STATIONARY)	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
0995000000-E	340	130	LF	PIPE REMOVAL	4405000000-E	1110	96	SF	WORK ZONE SIGNS (PORTABLE)	6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
1220000000-E	545	100	TON	INCIDENTAL STONE BASE	4410000000-E	1110	32	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6108000000-E	1665	0.25	TON	FERTILIZER TOPDRESSING
1330000000-E	607	540	SY	INCIDENTAL MILLING	4430000000-N	1130	49	EA	DRUMS	6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
1489000000-E	610	1,050	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4435000000-N	1135	25	EA	CONES	6123000000-E	1670	0.75	ACR	REFORESTATION
1498000000-E	610	675	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4455000000-N	1150	4	MD	FLAGGER					
1519000000-E	610	715	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4480000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)					
1560000000-E	620	127	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4650000000-N	1251	38	EA	TEMPORARY RAISED PAVEMENT MARKERS					
2286000000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES	4810000000-E	1205	19,520	LF	PAINT PAVEMENT MARKING LINES (4")					
2367000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29	4850000000-E	1205	900	LF	REMOVAL OF PAVEMENT MARKING LINES (4")					
2556000000-E	846	95	LF	SHOULDER BERM GUTTER	4900000000-N	1252	20	EA	PERMANENT RAISED PAVEMENT MARKERS					
3030000000-E	862	500	LF	STEEL BM GUARDRAIL	6000000000-E	1605	700	LF	TEMPORARY SILT FENCE					
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A					
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6009000000-E	1610	130	TON	STONE FOR EROSION CONTROL, CLASS B					

13-FEB-2004 10:53  
RD214492\_03\_139\_rdy-tyj-p.dgn  
BCKcell