

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200846

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS SUMMARY OF QUANTITIES

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+48.00)
004300000-N	226	Lump Sum		GRADING
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
005700000-E	226	2,500	CY	UNDERCUT EXCAVATION
013400000-E	240	1,530	CY	DRAINAGE DITCH EXCAVATION
019500000-E	265	1,500	CY	SELECT GRANULAR MATERIAL
019600000-E	270	1,500	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	75	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
036600000-E	310	276	LF	15" RC PIPE CULVERTS, CLASS III
037200000-E	310	88	LF	18" RC PIPE CULVERTS, CLASS III
058200000-E	310	264	LF	15" CS PIPE CULVERTS, 0.064" THICK
070800000-E	310	72	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
080600000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
099500000-E	340	464	LF	PIPE REMOVAL
112100000-E	520	2,000	TON	AGGREGATE BASE COURSE
122000000-E	545	300	TON	INCIDENTAL STONE BASE
127500000-E	600	1,040	GAL	PRIME COAT
129700000-E	607	515	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/4")
148900000-E	610	880	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
149800000-E	610	560	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B
151900000-E	610	875	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
156000000-E	620	125	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
169300000-E	654	40	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
200000000-N	806	22	EA	RIGHT OF WAY MARKERS
202200000-E	815	45	CY	SUBDRAIN EXCAVATION
203300000-E	815	35	CY	SUBDRAIN FINE AGGREGATE
204400000-E	815	200	LF	6" PERFORATED SUBDRAIN PIPE
205500000-E	815	6	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES
236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29
255600000-E	846	86	LF	SHOULDER BERM GUTTER
284500000-N	858	1	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
303000000-E	862	487.5	LF	STEEL BM GUARDRAIL
304500000-E	862	150	LF	STEEL BM GUARDRAIL, SHOP CURVED
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
319500000-N	862	3	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	1	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
336000000-E	863	265	LF	REMOVE EXISTING GUARDRAIL
364900000-E	876	195	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	1,130	SY	FILTER FABRIC FOR DRAINAGE
365900000-N	SP	3	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
402500000-E	901	6	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (D)

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
402500000-E	901	8.5	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	564800000-N	1510	1	EA	RELOCATE EXISTING WATER METER
407200000-E	903	68	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	567200000-N	1510	1	EA	RELOCATE EXISTING FIRE HYDRANT
409600000-N	904	2	EA	SIGN ERECTION, TYPE D	600000000-E	1605	850	LF	TEMPORARY SILT FENCE
410200000-N	904	2	EA	SIGN ERECTION, TYPE E	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
415500000-N	907	5	EA	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	600900000-E	1610	725	TON	STONE FOR EROSION CONTROL, CLASS B
415800000-N	907	2	EA	DISPOSAL OF SIGN SYSTEM, WOOD	601200000-E	1610	475	TON	SEDIMENT CONTROL STONE
443000000-N	1130	105	EA	DRUMS	601500000-E	1615	5	ACR	TEMPORARY MULCHING
443500000-N	1135	20	EA	CONES	601800000-E	1620	200	LB	SEED FOR TEMPORARY SEEDING
444500000-E	1145	280	LF	BARRICADES (TYPE III)	602100000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEED- ING
445500000-N	1150	180	MD	FLAGGER	602400000-E	1622	300	LF	TEMPORARY SLOPE DRAINS
446000000-N	1155	4	EA	WARNING LIGHTS (TYPE B)	602700000-N	1622	5	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
446500000-N	1160	1	EA	TEMPORARY CRASH CUSHIONS	603000000-E	1630	1,650	CY	SILT EXCAVATION
461500000-E	1205	1,320	LF	REMOVABLE TAPE PAVEMENT MARK- ING LINES (4")	603600000-E	1631	1,575	SY	MATting FOR EROSION CONTROL
465000000-N	1251	100	EA	TEMPORARY RAISED PAVEMENT MARKERS	604200000-E	1632	50	LF	1/4" HARDWARE CLOTH
468500000-E	1205	3,520	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	607000000-N	SP	12	EA	SPECIAL STILLING BASINS
468600000-E	1205	3,520	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	608400000-E	1660	7	ACR	SEEDING & MULCHING
477000000-E	1205	1,320	LF	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (4")	608700000-E	1660	3	ACR	MOWING
481000000-E	1205	23,960	LF	PAINT PAVEMENT MARKING LINES (4")	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
490000000-N	1252	27	EA	PERMANENT RAISED PAVEMENT MARKERS	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
530000000-E	1505	1	TON	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (VI)	609600000-E	1662	125	LB	SEED FOR SUPPLEMENTAL SEEDING
530600000-E	SP	1	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	610800000-E	1665	5.25	TON	FERTILIZER TOPDRESSING
536000000-E	1510	16	LF	6" DI WATER PIPE, PC 350	611400000-N	SP	1	HR	SPECIALIZED HAND MOWING
554000000-E	1510	1	EA	6" GATE VALVE & VALVE BOX, 200# WP	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL