

DIVISION OF HIGHWAYS
 STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
13+00.00 TO 14+00.00 -L- LT. SIDE	3		53	50	0
13+00.00 TO 14+00.00 -L- RT. SIDE	228		23	0	205
14+00.00 TO 16+10.00 -L-	30		1015	987	2
17+15.00 TO 18+85.00 -L-	34		1011	979	2
18+85.00 TO 20+75.00 -L- LT. SIDE	76		133	61	4
18+85.00 TO 20+75.00 -L- RT. SIDE	34		36	4	2
SUMMARIES TOTAL	405		2271	2080	214
WASTE TO BE USED IN LIEU OF BORROW				-194	-194
PROJECT TOTAL	405			1886	20
EST. FOR REPLACEMENT OF TOPSOIL AT BORROW PIT				94	
GRAND TOTAL	405			1981	
SAY	425			2000	
ESTIMATED UNDERCUT	200				

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, breaking of existing asphalt pavement, and removal of existing asphalt pavement will be paid for at the contract lump sum price for "Grading".

SUMMARY OF ASPHALT PAVEMENT REMOVAL

IN SQUARE YARDS

LINE	STATION TO STATION	LOCATION	ASPHALT REMOVAL
-L-	14+00.00 TO 14+75.00	CENTERLINE	166.67
-L-	16+00.00 TO 16+48.16	CENTERLINE	107.02
-L-	16+83.17 TO 17+35.00	CENTERLINE	115.18
-L-	18+15.00 TO 18+85.00	CENTERLINE	155.56
		TOTAL	544.42
		SAY	550

SUMMARY OF ASPHALT PAVEMENT BREAKING

IN SQUARE YARDS

LINE	STATION TO STATION	LOCATION	ASPHALT REMOVAL
-L-	14+75.00 TO 16+00.00	CENTERLINE	277.78
-L-	17+35.00 TO 18+15.00	CENTERLINE	117.78
		TOTAL	455.56
		SAY	460

6/4/99
 17-AUG-2004 09:19
 W:\Projects\2004\B-3871\RDY-SUMMARIES.dgn