

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+67.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	16 LF		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	306 LF		
0011	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	32 LF		
0012	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0013	0995000000-E	340	PIPE REMOVAL	351 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	6 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	340 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	400 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	330 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	480 TON		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	62 TON		
0020	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0021	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	170 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	450 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0028	3649000000-E	876	PLAIN RIP RAP, CLASS B	5 TON		
0029	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	165 SY		
0030	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	303 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0033	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0034	4445000000-E	1145	BARRICADES (TYPE III)	56 LF		
0035	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,202 LF		
0036	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	10 EA		
0037	6000000000-E	1605	TEMPORARY SILT FENCE	750 LF		

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150 TON		
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0044	6030000000-E	1630	SILT EXCAVATION	275 CY		
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	675 SY		
0046	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0047	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0048	6087000000-E	1660	MOWING	0.5 ACR		
0049	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0050	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0051	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0052	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0053	6114000000-N	SP	SPECIALIZED HAND MOWING	0.5 HR		
0054	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

STRUCTURE ITEMS

0055	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+67.50-L-)	Lump Sum	L.S.	
------	--------------	-----	---	----------	------	--

County : Martin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+67.50-L-)	Lump Sum	L.S.	
0057	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	41.5 CY		
0058	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+67.50-L-)	Lump Sum	L.S.	
0059	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,912 LB		
0060	8364000000-E	450	HP12X53 STEEL PILES	1,395 LF		
0061	8384000000-E	450	HP14X73 STEEL PILES	560 LF		
0062	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (16+67.50-L-)	Lump Sum	L.S.	
0063	8503000000-E	460	CONCRETE BARRIER RAIL	185.25 LF		
0064	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	187 TON		
0065	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	208 SY		
0066	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0067	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,296.75 LF		

1345/Aug19/Q23605.5/D291067100000/E67

Total Amount Of Bid For Entire Project :

C201264
MARTIN

2/16/99

Contract No: C201264

Counties: Martin

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General