

## SUMMARY OF EARTHWORK IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBT + %	BORROW	WASTE
-L- 12+45 - 18+18 (BEGIN BRIDGE)	1094	1511	417	
-L- 19+23 (END BRIDGE)- 23+04.81	7	13168	13161	
PROJECT TOTALS	1101	14679	13578	
EST. 5% FOR REPLACING TOP SOIL ON BORROW PITS			679	
GRAND TOTAL	1101		14257	
SAY	1110		14300	

UNDERCUT = 350 CU. YDS.  
 DRAINAGE DITCH EXCAVATION = 700 CU. YDS.  
 PAVEMENT STRUCTURE VOLUME: 90 CU. YDS.

NOTE:  
 APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION,  
 FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL  
 OF EXISTING PAVEMENT WILL BE PAID FOR AT THE LUMP SUM  
 PRICE FOR "GRADING".

## SUMMARY OF SHOULDER BERM GUTTER

LINE	STATION TO STATION	LOCATION	LENGTH (FT)
-L-	17+83.33 TO 17+90.08	RT.	6.75
-L-	19+52.52 TO 21+77.00	LT.	224.48
		TOTAL	231.23
		SAY	235