




PAVEMENT SCHEDULE


C1	PROP. APPROX. 2½" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 138 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.	P1	PRIME COAT AT THE RATE OF .35 GAL. PER SQ. YD.
C2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 110 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 1½" IN DEPTH.	T	EARTH MATERIAL.
E1	PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.	U	EXISTING PAVEMENT.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH.	W	VARIABLE DEPTH ASPHALT PAVEMENT (SEE WEDGING DETAIL)
J1	PROP. 8" AGGREGATE BASE COURSE.		

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.

PROJECT REFERENCE NO. B-3690	SHEET NO. 2
ROADWAY DESIGN ENGINEER	PAVEMENT DESIGN ENGINEER
	




Detail Showing Method of Wedging



TYPICAL SECTION NO. 1


USE TYPICAL SECTION NO. 1 FOR:
 -L- STA. 13+67.00 TO -L- STA. 16+21.58
 -L- STA. 18+60.42 TO -L- STA. 23+00.00



TYPICAL SECTION NO. 2

USE TYPICAL SECTION NO. 2 FOR:
 -L- STA. 12+80.00 TO -L- STA. 13+67.00

NOTE: TRANSITION FROM EXISTING TO TYPICAL SECTION NO. 2
 -L- STA. 12+00.00 TO -L- STA. 12+80.00



TYPICAL SECTION NO. 3

USE TYPICAL SECTION NO. 3 FOR:
 -DRI- STA. 10+12 TO -DRI- STA. 11+50