

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+41.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	90 CY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	19 TON		
0008	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	52 LF		
0009	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	96 LF		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0011	0995000000-E	340	PIPE REMOVAL	88 LF		
0012	1121000000-E	520	AGGREGATE BASE COURSE	130 TON		
0013	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0014	1275000000-E	600	PRIME COAT	100 GAL		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	430 TON		
0016	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	350 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	42 TON		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	15 LF		
0021	3030000000-E	862	STEEL BM GUARDRAIL	375 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0025	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	900 LF		
0026	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	55 EA		
0027	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	25 EA		
0028	3575000000-E	SP	GENERIC FENCING ITEM THREE STRAND ELECTRIC FENCE (COMPLETE WITH POSTS)	400 LF		
0029	3649000000-E	876	PLAIN RIP RAP, CLASS B	35 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	960 SY		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	96 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	90 SF		
0033	4430000000-N	1130	DRUMS	30 EA		
0034	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0035	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	17,600 LF		
0036	6000000000-E	1605	TEMPORARY SILT FENCE	370 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0038	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	325 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	460 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	190 LF		
0044	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	6 EA		
0045	6030000000-E	1630	SILT EXCAVATION	835 CY		
0046	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,170 SY		
0047	6070000000-N	SP	SPECIAL STILLING BASINS	16 EA		
0048	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0049	6087000000-E	1660	MOWING	0.5 ACR		
0050	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0051	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0052	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0053	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0054	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0055	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0056	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+41.00-L-)	Lump Sum	L.S.	
0057	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+41.00-L-)	Lump Sum	L.S.	
0058	8096000000-E	SP	PILE EXCAVATION IN SOIL	15 LF		
0059	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	15 LF		
0060	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	33 LF		
0061	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	76 LF		
0062	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	15.2 LF		
0063	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0064	8116000000-E	SP	CSL TUBES	516 LF		
0065	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	8,345 SF		
0066	8161000000-E	420	GROOVING BRIDGE FLOORS	8,256 SF		
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	138.7 CY		
0068	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+41.00-L-)	Lump Sum	L.S.	
0069	8217000000-E	425	REINFORCING STEEL (BRIDGE)	30,075 LB		
0070	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,745 LB		
0071	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	1,164.17 LF		
0072	8364000000-E	450	HP12X53 STEEL PILES	195 LF		
0073	8503000000-E	460	CONCRETE BARRIER RAIL	473.5 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	535 TON		
0075	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	595 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1342/Aug04/Q81277.82/D377786680000/E77			Total Amount Of Bid For Entire Project :			

Contract No: **C200962**

Counties: **Randolph**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General