

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB-BING	0.4 HA		
0005	0057000000-M	226	UNDERCUT EXCAVATION	765 M3		
0006	0134000000-M	240	DRAINAGE DITCH EXCAVATION	25 M3		
0007	0318000000-M	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	150 MTN		
0008	0344000000-M	310	450MM SIDE DRAIN PIPE	6 M		
0009	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	163.2 M		
0010	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	243.6 M		
0011	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	38.4 M		
0012	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	7.2 M		
0013	0708000000-M	310	400MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	15.6 M		
0014	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	2 EA		
0015	0995000000-M	340	PIPE REMOVAL	183 M		
0016	1220000000-M	545	INCIDENTAL STONE BASE	250 MTN		
0017	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,110 MTN		
0018	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,115 MTN		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,270 MTN		
0020	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	177 MTN		
0021	1693000000-M	654	ASPHALT PLANT MIX PAVEMENT REPAIR	60 MTN		
0022	2253000000-M	840	PIPE COLLARS	1 M3		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	26 EA		
0024	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	5 M		
0025	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.37)	1 EA		
0026	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0028	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	4 EA		
0029	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	6 EA		
0030	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	10 EA		
0031	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0032	2500000000-M	842	CONCRETE RETAINING WALLS	15 M3		
0033	2535000000-M	846	*** X ***MM CONCRETE CURB (200MM X 450MM)	185 M		
0034	2549000000-M	846	750MM CONCRETE CURB & GUTTER	915 M		
0035	2612000000-M	848	150MM CONCRETE DRIVEWAY	125 M2		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2830000000-N	858	ADJUSTMENT OF MANHOLES	4 EA		
0037	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0038	3030000000-M	862	STEEL BM GUARDRAIL	339.09 M		
0039	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0040	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0041	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0042	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0043	3360000000-M	863	REMOVE EXISTING GUARDRAIL	350.071 M		
0044	3536000000-M	866	CHAIN LINK FENCE, 1200MM FABRIC	215 M		
0045	3542000000-M	866	METAL LINE POSTS FOR 1200MM CHAIN LINK FENCE	65 EA		
0046	3548000000-M	866	METAL TERMINAL POSTS FOR 1200MM CHAIN LINK FENCE	15 EA		
0047	3628000000-M	876	PLAIN RIP RAP, CLASS I	17 MTN		
0048	3649000000-M	876	PLAIN RIP RAP, CLASS B	10 MTN		
0049	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	275 M2		
0050	4025000000-M	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	0.55 M2		
0051	4025000000-M	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	4.7 M2		
0052	4078000000-M	903	SUPPORTS, 3KG STEEL U-CHANNEL	51 EA		
0053	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4102000000-N	904	SIGN ERECTION, TYPE E	8 EA		
0055	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	1 EA		
0056	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	13 EA		
0057	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	4 EA		
0058	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0059	4430000000-N	1130	DRUMS	120 EA		
0060	4435000000-N	1135	CONES	80 EA		
0061	4445000000-M	1145	BARRICADES (TYPE III)	40 M		
0062	4455000000-N	1150	FLAGGER	345 MD		
0063	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	40 EA		
0064	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	328 M		
0065	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	1,748 M		
0066	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	56 M		
0067	4705000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (400MM, 3.1MM)	14 M		
0068	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	8 M		
0069	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	2 EA		
0070	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	12 EA		
0071	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (100MM)	144 M		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	1,716 M		
0073	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	144 EA		
0074	5300000000-M	1505	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (VI)	80 MTN		
0075	5306000000-M	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	80 MTN		
0076	5318000000-M	1505	PAVEMENT REPAIR FOR UTILITY WORK	48.7 MTN		
0077	5336000000-M	1510	200MM DI WATER PIPE, CLASS ***** WP (51, PC 2.41MPA)	252.2 M		
0078	5360000000-M	1510	150MM DI WATER PIPE, PC 2.41MPA	88.4 M		
0079	5402000000-M	1510	DI RESTRAINED JOINT WATER PIPE FITTINGS, 1.72MPA MIN WP	165.4 KG		
0080	5408000000-M	1510	***MM COPPER WATER PIPE, TYPE K (50MM)	63.1 M		
0081	5414000000-M	1510	20MM COPPER WATER PIPE, TYPE K	38.1 M		
0082	5480000000-M	1510	DUCTILE IRON WATER PIPE FIT- TINGS, 1.72MPA MIN WP	740 KG		
0083	5504000000-M	1510	***MM CORPORATION STOP (20MM)	3 EA		
0084	5504000000-M	1510	***MM CORPORATION STOP (50MM)	2 EA		
0085	5534000000-M	1510	***MM GATE VALVE & VALVE BOX, ****MPA WP (50MM, 1.38MPA WP)	1 EA		
0086	5540000000-M	1510	150MM GATE VALVE & VALVE BOX, 1.38MPA WP	4 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	5546000000-M	1510	200MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA WP)	2 EA		
0088	5558000000-M	1510	300MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA WP)	1 EA		
0089	5582000000-M	1510	*** X ***MM TAPPING SADDLE (150MM X 20MM)	1 EA		
0090	5582000000-M	1510	*** X ***MM TAPPING SADDLE (200MM X 50MM)	2 EA		
0091	5582000000-M	1510	*** X ***MM TAPPING SADDLE (300MM X 20MM)	2 EA		
0092	5648000000-N	1510	RELOCATE EXISTING WATER METER	3 EA		
0093	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	3 EA		
0094	5864000000-M	SP	450MM STEEL ENCASEMENT PIPE, ****MM THICK, BY BORING & JACKING (7.92MM)	43 M		
0095	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXT 50MM WATER METER	2 EA		
0096	5882000000-N	SP	GENERIC UTILITY ITEM THRUST COLLAR	2 EA		
0097	6000000000-M	1605	TEMPORARY SILT FENCE	800 M		
0098	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	105 MTN		
0099	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	365 MTN		
0100	6012000000-M	1610	SEDIMENT CONTROL STONE	255 MTN		
0101	6015000000-M	1615	TEMPORARY MULCHING	1.5 HA		
0102	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	75 KG		
0103	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 MTN		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	6024000000-M	1622	TEMPORARY SLOPE DRAINS	50 M		
0105	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0106	6030000000-M	1630	SILT EXCAVATION	430 M3		
0107	6036000000-M	1631	MATTING FOR EROSION CONTROL	1,530 M2		
0108	6042000000-M	1632	6.4MM HARDWARE CLOTH	200 M		
0109	6084000000-M	1660	SEEDING & MULCHING	2 HA		
0110	6087000000-M	1660	MOWING	1 HA		
0111	6090000000-M	1661	SEED FOR REPAIR SEEDING	25 KG		
0112	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.25 MTN		
0113	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	50 KG		
0114	6108000000-M	1665	FERTILIZER TOPDRESSING	2.75 MTN		
0115	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0116	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

**WALL ITEMS**

0117	8800000000-N	SP	MSE RETAINING WALL, STA ***** (12+92.508 -L- WALL 1)	Lump Sum	L.S.	
0118	8800000000-N	SP	MSE RETAINING WALL, STA ***** (12+92.508 -L- WALL 2)	Lump Sum	L.S.	
0119	8800000000-N	SP	MSE RETAINING WALL, STA ***** (12+92.508 -L- WALL 3)	Lump Sum	L.S.	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0120	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+92.508 -L-)	Lump Sum	L.S.	
0121	8119000000-M	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,400 M3		
0122	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	582.8 M2		
0123	8161000000-M	420	GROOVING BRIDGE FLOORS	597.8 M2		
0124	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	61.5 M3		
0125	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+92.508 -L-)	Lump Sum	L.S.	
0126	8217000000-M	425	REINFORCING STEEL (BRIDGE)	6,244 KG		
0127	8280000000-M	440	APPROX ..... KG STRUCTURAL STEEL	81,900 LS		
0128	8364000000-M	450	HP310X79 STEEL PILES	567 M		
0129	8482000000-M	460	THREE BAR METAL RAIL	66.02 M		

1332/Aug06/Q110036.081/D557903500000/E129

Total Amount Of Bid For Entire Project :



C200811  
WAKE COUNTY

2/16/99

Contract No: C200811

Counties: Wake County

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General