

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200713

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
004300000-N	226	Lump Sum		GRADING
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
034200000-E	310	16	LF	** SIDE DRAIN PIPE (15")
070800000-E	310	28	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
080600000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK (15", 0.064")
098600000-E	SP	16	LF	GENERIC PIPE ITEM 12" CS SLOTTED DRAIN, 0.064" THICK
112100000-E	520	42	TON	AGGREGATE BASE COURSE
122000000-E	545	10	TON	INCIDENTAL STONE BASE
148900000-E	610	155	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
149800000-E	610	210	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B
151900000-E	610	150	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
156000000-E	620	30	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
169300000-E	654	10	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
228600000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
237400000-N	840	1	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)
254900000-E	846	200	LF	2'-6" CONCRETE CURB & GUTTER
259100000-E	848	112	SY	4" CONCRETE SIDEWALK
303000000-E	862	375	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
362800000-E	876	50	TON	PLAIN RIP RAP, CLASS I

ItemNumber	Sec #	Quantity	Unit	Description
364900000-E	876	13	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	615	SY	FILTER FABRIC FOR DRAINAGE
441200000-E	SP	340	SF	WORK ZONE SIGNS (STATIONARY)
441220000-E	SP	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
442500000-N	1125	2	EA	WARNING FLAG SETS
444610000-E	SP	80	LF	BARRICADES (TYPE III)
468500000-E	1205	604	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
468600000-E	1205	604	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
490000000-N	1252	8	EA	PERMANENT RAISED PAVEMENT MARKERS
530000000-E	1505	10	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (IV)
530600000-E	SP	10	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)
555800000-E	1510	2	EA	12" GATE VALVE & VALVE BOX, *****WP (200#)
588800000-E	SP	187	LF	GENERIC UTILITY ITEM 12" DI RESTRAINED JOINT WATER PIPE, PC 350
588800000-E	SP	27	LF	GENERIC UTILITY ITEM CONCRETE ARCH ENCASEMENT FOR SEWER PIPE
590600000-E	SP	1,020	LB	GENERIC UTILITY ITEM DUCTILE IRON RESTRAINED JOINT WATER PIPE FITTINGS, 250 PSI MN WP
600000000-E	1605	290	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	90	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	30	TON	SEDIMENT CONTROL STONE
601500000-E	1615	1	ACR	TEMPORARY MULCHING
601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING

ItemNumber	Sec #	Quantity	Unit	Description
602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
602400000-E	1622	20	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
602900000-E	SP	150	LF	SAFETY FENCE
603000000-E	1630	225	CY	SILT EXCAVATION
603300000-E	1631	114	SY	SYNTHETIC ROVING
603600000-E	1631	368	SY	MATTING FOR EROSION CONTROL
604200000-E	1632	20	LF	1/4" HARDWARE CLOTH
606900000-E	1638	100	CY	STILLING BASINS
608400000-E	1660	1	ACR	SEEDING & MULCHING
608700000-E	1660	0.5	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	0.75	TON	FERTILIZER TOPDRESSING
611000000-E	SP	150	LF	IMPERVIOUS DIKE
611400000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
612000000-E	SP	462	CY	CULVERT DIVERSION CHANNEL

5/28/99

19-001-2004 14:14
W:\TIP_Proj\proj\11\es\Stroup\B-3424\proj\CURR\PLANS\1007\PLANS\B-3424.sum
stroup_HL_DS212420