

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0342000000-E	310	*** SIDE DRAIN PIPE (15")	16 LF		
0006	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	28 LF		
0007	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK (15", 0.064")	2 EA		
0008	0986000000-E	SP	GENERIC PIPE ITEM 12" CS SLOTTED DRAIN, 0.064" THICK	16 LF		
0009	1121000000-E	520	AGGREGATE BASE COURSE	42 TON		
0010	1220000000-E	545	INCIDENTAL STONE BASE	10 TON		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	155 TON		
0012	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	210 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	150 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	30 TON		
0015	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
0016	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0017	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	200 LF		
0019	2591000000-E	848	4" CONCRETE SIDEWALK	112 SY		
0020	3030000000-E	862	STEEL BM GUARDRAIL	375 LF		
0021	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0022	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0023	3628000000-E	876	PLAIN RIP RAP, CLASS I	50 TON		
0024	3649000000-E	876	PLAIN RIP RAP, CLASS B	13 TON		
0025	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	615 SY		
0026	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	340 SF		
0027	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0028	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0029	4446100000-E	SP	BARRICADES (TYPE III)	80 LF		
0030	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	604 LF		
0031	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	604 LF		
0032	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	8 EA		
0033	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (IV)	10 TON		
0034	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	10 TON		
0035	5558000000-E	1510	12" GATE VALVE & VALVE BOX, *****WP (200#)	2 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	5888000000-E	SP	GENERIC UTILITY ITEM 12" DI RESTRAINED JOINT WATER PIPE,PC 350	187 LF		
0037	5888000000-E	SP	GENERIC UTILITY ITEM CONCRETE ARCH ENCASEMENT FOR SEWER PIPE	27 LF		
0038	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON RESTRAINED JOINT WATER PIPE FITTINGS, 250 PSI MIN WP	1,020 LB		
0039	6000000000-E	1605	TEMPORARY SILT FENCE	290 LF		
0040	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90 TON		
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	30 TON		
0043	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0045	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	20 LF		
0047	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0048	6029000000-E	SP	SAFETY FENCE	150 LF		
0049	6030000000-E	1630	SILT EXCAVATION	225 CY		
0050	6033000000-E	1631	SYNTHETIC ROVING	114 SY		
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	368 SY		
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0053	6069000000-E	1638	STILLING BASINS	100 CY		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6084000000-E	1660	SEEDING & MULCHING	1	ACR	
0055	6087000000-E	1660	MOWING	0.5	ACR	
0056	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0057	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0058	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0059	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75	TON	
0060	6111000000-E	SP	IMPERVIOUS DIKE	150	LF	
0061	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5	HR	
0062	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8	EA	
0063	6120000000-E	SP	CULVERT DIVERSION CHANNEL	462	CY	
CULVERT ITEMS						
0064	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+14.000 -L-)	Lump Sum	L.S.	
0065	8063000000-N	SP	PRECAST REINFORCED CONC BOX CULVERT AT STA ***** (13+14.000 -L-)	Lump Sum	L.S.	
0066	8126000000-N	414	CULVERT EXCAVATION, STA ***** (13+14.000 -L-)	Lump Sum	L.S.	
0067	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	166	TON	

0953/Dec03/Q7464.25/D292764800000/E67

Total Amount Of Bid For Entire Project :

C200713 (B-3424)
CABBARUS COUNTY

2/16/99

Contract No: C200713

County: Cabarrus

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General