

| PROJECT NO. | SHEET NO. | TOTAL NO. |
|--------------------------|-----------|-----------|
| 8CR.10191.3, 8CR.20191.3 | 3 | 5 |
| 8CR.301939.3, | | |

SUMMARY OF QUANTITIES

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LENGTH MI | WIDTH FT | INCIDENTAL STONE BASE TONS | SHOULDER RECONSTRUCTION SMI | INCIDENTAL MILLING SY | SURFACE COURSE, S9.5B TONS | SURFACE COURSE, S9.5C TONS | PG 64-22 PLANT MIX TONS | PG 70-22 PLANT MIX TONS | PATCHING EXISTING PAVEMENT TONS | ADJUST MANHOLES EA | SEED & MULCHING AC |
|--|---------|--------|---------|--|--------|--------------|----------|----------------------------|-----------------------------|-----------------------|----------------------------|----------------------------|-------------------------|-------------------------|---------------------------------|--------------------|--------------------|
| 8CR.10191.3 | Chatham | 1 | NC 902 | FROM SR 1506 TO SR 1010 | 1 & 3 | 3 | 20 | 100 | 6 | 400 | | 2,680 | | 161 | 100 | | 3.75 |
| TOTAL FOR PROJ NO. 8CR.10191.3 | | | | | | 3 | | 100 | 6 | 400 | | 2,680 | | 161 | 100 | | 3.75 |
| 8CR.20191.3 | Chatham | 2 | SR 1151 | FROM SR 1005 TO SR 1154 | 2 | 3.79 | 22 | 100 | 7.58 | 533 | 4506 | | 270 | | 100 | | 4.74 |
| | | 3 | SR 2303 | FROM SR 2309 TO GOLDSTON CL | 2 | 3.6 | 18 | 100 | 7.2 | 533 | 4280 | | 257 | | 100 | | 4.50 |
| TOTAL FOR PROJ NO. 8CR.20191.3 | | | | | | 7.39 | | 200 | 14.78 | 1066 | 8786 | | 527 | | 200 | | 9.24 |
| 8CR.301939.3 | Chatham | 4 | SR 1006 | FROM SCL SILER CITY TO PAVEMENT WIDENING | 1 | 0.57 | 24 | 25 | 1.14 | 533 | | 678 | | 41 | 25 | | 0.71 |
| | | 5 | SR 1107 | FROM SR 1006 TO US 64 | 1 | 1.06 | 26 | 25 | 2.12 | 578 | | 1,365 | | 82 | | 4 | 1.33 |
| TOTAL FOR PROJ NO. 8CR.301939.3 | | | | | | 1.63 | | 50 | 3.26 | 1111 | 0 | 2,043 | | 123 | 25 | 4 | 2.04 |
| GRAND TOTAL | | | | | | 12.02 | | 350 | 24.04 | 2577 | 8786 | 4,723 | 527 | 284 | 325 | 4 | 15.03 |