

EB1-A

SOIL TEST RESULTS														
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE
							C.SAND	F.SAND	SILT	CLAY	10	40	200	
SS-5	7' LT	14+48	3.7-5.2	A-6(4)	33	11	7.9	46.0	27.8	18.3	100	97	56	-
SS-6	7' LT	14+48	8.7-10.2	A-4(0)	23	5	26.4	31.6	23.7	18.3	97	84	47	22.9
SS-7	7' LT	14+48	13.7-15.2	A-6(6)	30	13	6.5	34.1	31.0	28.4	100	97	66	-

EB1-B

SOIL TEST RESULTS														
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE
							C.SAND	F.SAND	SILT	CLAY	10	40	200	
SS-8	21' RT	14+32	3.0-4.5	A-6(4)	34	15	16.8	40.6	22.3	20.3	100	92	50	-
SS-9	21' RT	14+32	13.5-14.5	A-2-4(0)	19	NP	39.8	36.7	11.4	12.2	100	87	27	-

B1-B

SOIL TEST RESULTS														
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE
							C.SAND	F.SAND	SILT	CLAY	10	40	200	
SS-13	8' RT	14+69	9.7-11.2	A-4(3)	25	6	4.7	26.8	44.2	24.3	100	98	78	27.7
SS-14	8' RT	14+69	15.2-16.2	A-7-6(19)	45	25	6.7	18.7	32.0	42.6	98	95	77	-

B2-A

SOIL TEST RESULTS														
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE
							C.SAND	F.SAND	SILT	CLAY	10	40	200	
SS-11	8' LT	15+29	4.7-6.2	A-2-4(0)	19	NP	28.0	45.8	14.0	12.2	96	85	31	-
SS-12	8' LT	15+29	10.3-11.2	A-6(17)	40	18	3.7	11.2	44.6	40.6	100	98	89	-

EB2-A

SOIL TEST RESULTS														
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE
							C.SAND	F.SAND	SILT	CLAY	10	40	200	
SS-1	8' LT	15+59	3.7-4.8	A-2-4(0)	22	7	35.9	32.7	13.2	18.3	95	74	34	-
SS-2	8' LT	15+59	4.8-5.2	A-7-6(10)	48	26	25.2	24.9	13.4	36.5	100	87	53	-
SS-3	8' LT	15+59	8.7-10.2	A-4(2)	25	8	16.6	30.4	30.6	22.3	92	84	54	-
SS-4	8' LT	15+59	13.7-15.2	A-6(6)	34	15	11.2	37.9	22.5	28.4	99	97	56	-

EB2-B

SOIL TEST RESULTS														
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE
							C.SAND	F.SAND	SILT	CLAY	10	40	200	
SS-10	18' RT	15+43	13.6-15.1	A-6(3)	34	18	39.6	20.7	13.4	26.4	95	72	40	-