

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200852

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+99.30)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0057000000-E	226	300	CY	UNDERCUT EXCAVATION
0318000000-E	300	17	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0366000000-E	310	52	LF	15" RC PIPE CULVERTS, CLASS III
0372000000-E	310	88	LF	18" RC PIPE CULVERTS, CLASS III
0708000000-E	310	20	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0995000000-E	340	81.5	LF	PIPE REMOVAL
1330000000-E	607	180	SY	INCIDENTAL MILLING
1489000000-E	610	910	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	1,000	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	840	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	140	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	30	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	8	EA	RIGHT OF WAY MARKERS
2253000000-E	840	1	CY	PIPE COLLARS
2286000000-N	840	5	EA	MASONRY DRAINAGE STRUCTURES
2308000000-E	840	3.17	LF	MASONRY DRAINAGE STRUCTURES
2352000000-N	840	3	EA	FRAME WITH GRATE, STD 840.**** (840.16)
2367000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29
ItemNumber	Sec #	Quantity	Unit	Description
2556000000-E	846	50	LF	SHOULDER BERM GUTTER
2570000000-N	SP	2	EA	MODIFIED CONCRETE FLUME
2580000000-E	846	224	LF	CONCRETE VALLEY GUTTER CONCRETE VALLEY GUTTER
2619000000-E	850	15	SY	4" CONCRETE PAVED DITCH
2724000000-E	857	240	LF	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED
3030000000-E	862	826.5	LF	STEEL BM GUARDRAIL
3045000000-E	862	262.5	LF	STEEL BM GUARDRAIL, SHOP CURVED
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3195000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3317000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77
3360000000-E	863	481	LF	REMOVE EXISTING GUARDRAIL
3628000000-E	876	2	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	20	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	466	SY	FILTER FABRIC FOR DRAINAGE
4025000000-E	901	15.75	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
4072000000-E	903	29	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
4102000000-N	904	3	EA	SIGN ERECTION, TYPE E
4155000000-N	907	4	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
4412000000-E	SP	184	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	176	SF	WORK ZONE SIGNS (PORTABLE)
4420000000-N	1120	2	EA	CHANGEABLE MESSAGE SIGNS
4430000000-N	1130	20	EA	DRUMS
4446100000-E	SP	160	LF	BARRICADES (TYPE III)

ItemNumber	Sec #	Quantity	Unit	Description
4450000000-N	1150	480	HR	FLAGGER
4650000000-N	1251	35	EA	TEMPORARY RAISED PAVEMENT MARKERS
4685000000-E	1205	2,500	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4686000000-E	1205	3,110	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4695000000-E	1205	160	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
4710000000-E	1205	170	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
4725000000-E	1205	2	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
4810000000-E	1205	12,480	LF	PAINT PAVEMENT MARKING LINES (4")
4820000000-E	1205	320	LF	PAINT PAVEMENT MARKING LINES (8")
4835000000-E	1205	340	LF	PAINT PAVEMENT MARKING LINES (24")
4900000000-N	1252	35	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	500	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	465	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6029000000-E	SP	300	LF	SAFETY FENCE
6030000000-E	1630	200	CY	SILT EXCAVATION
6036000000-E	1631	855	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	1,100	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	6	EA	SPECIAL STILLING BASINS
6084000000-E	1660	1.5	ACR	SEEDING & MULCHING
ItemNumber	Sec #	Quantity	Unit	Description
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
7060000000-E	1705	4,195	LF	SIGNAL CABLE
7120000000-E	1705	44	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
7144000000-E	1705	4	EA	VEHICLE SIGNAL HEAD (12", 5 SECTION)
7252000000-E	1710	400	LF	MESSENGER CABLE (1/4")
7264000000-E	1710	1,210	LF	MESSENGER CABLE (3/8")
7279000000-E	1715	5,500	LF	TRACER WIRE
7300000000-E	1715	6,395	LF	TRENCHING (UNPAVED)
7301000000-E	SP	945	LF	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 2)
7302000000-E	SP	400	LF	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, 1-1/4" (** CONDUIT) (1)
7324000000-N	1716	23	EA	JUNCTION BOX (STANDARD SIZE)
7336000000-N	1716	18	EA	JUNCTION BOX (OVER-SIZED)
7360000000-N	1720	6	EA	WOOD POLE
7372000000-N	1721	18	EA	GUY ASSEMBLY
7408000000-E	1722	2	EA	1" RISER WITH WEATHERHEAD
7420000000-E	1722	5	EA	2" RISER WITH WEATHERHEAD
7432000000-E	1722	4	EA	2" RISER WITH HEAT SHRINK TUBING
7444000000-E	1725	2,325	LF	INDUCTIVE LOOP SAWCUT
7456000000-E	1726	2,825	LF	LEAD-IN CABLE
7516000000-E	1730	7,500	LF	COMMUNICATIONS CABLE (**FIBER) (12)

ItemNumber	Sec #	Quantity	Unit	Description
7552000000-N	1731	3	EA	INTERCONNECT CENTER
7566000000-N	1733	8	EA	DELINEATOR MARKER
7568000000-N	SP	1	EA	FURNISH FIBER-OPTIC RESTORATION KIT
7574000000-N	SP	1	EA	FURNISH FIBER-OPTIC TRANSCEIVER
7575160000-E	SP	500	LF	REMOVE EXISTING COMMUNICATIONS CABLE
7588000000-N	1741	10	EA	SIGNAL SUPPORT MAST ARM WITH METAL POLE
7590000000-N	SP	1	EA	DOUBLE MAST ARM WITH METAL POLE
7613000000-N	SP	11	EA	SOIL TEST
7614000000-E	SP	165	LF	DRILLED PIER FOUNDATION (** DIA) (42")
7631000000-N	1744	11	EA	MAST ARM WITH METAL POLE DESIGN
7636000000-N	1745	18	EA	SIGN FOR SIGNALS
7684000000-N	1750	5	EA	SIGNAL CABINET FOUNDATION
7720000000-N	1751	3	EA	CONTROLLER WITH CABINET (TYPE 170E, BASE MOUNTED)
7740000000-N	SP	13	EA	DETECTOR CARD (TYPE 170)
7980000000-N	SP	4	EA	GENERIC SIGNAL ITEM FIBER-OPTIC TRANSCEIVER - SELF HEALING RING
8990000000-N	SP	1,000	DOL	CONTRACT TIME

5/28/99