MULKEY
ENGINEERS & CONSULTANTS
PO Box 33127
RALEIGH, N.C. 27636
(919) 851-1912
(919) 851-1918 (FAX)
WWW.MULKEYINC.COM

PROJ. REFERENCE NO.	SHEET NO.
B-3651	PM-1

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	FINAL	PAY ITEM QUANITY BREAKDOWN		TOTAL QUANTITY	
		PAVEMENT MARKINGS				
		PAINT (4")				
PA	WHITE EDGELINE (2X)		264	LF		
PF	10 FT. YELLOW SKIP (2X)		1109	LF		
PH	YELLOW SINGLE CENTER (2X)		4418	LF		
PI	YELLOW DOUBLE CENTER (2X)		5112	LF		
				TOTAL	10903	LF
		PAINT (8")				
PV	YELLOW DIAGONAL (2X)		133	LF		
				TOTAL	133	LF
		PAINT (24")				
P4	WHITE STOPBAR (2X)		167	LF		
				TOTAL	167	LF
		PAINT MARKING SYMBOLS				
QA	LEFT TURN ARROW (2X)		8	EA		
				TOTAL	8	EA

Kevin W. Bisby
NORTH CAROLINA PROFESSIONAL SEAL 21047 ENGINEER KEVIN W. BISBY
2-3-2004

FINAL PAVEMENT MARKINGS

SCALE:	NONE
DATE:	FEB 2004
DWG. BY:	MGH
DESIGN BY:	KWB
REVIEWED BY:	MHS

DIVISION OF HIGHWAYS TRAFFIC ENGINEERING BRANCH TRAFFIC CONTROL UNIT

REVISIONS

CADD FILE

02/03/2004 10:10:26 PM G:\Project\00Z\N8400 B-3651\Traffic Control\B3651PM.dgn