COMPUTED BY: L.N. MAGUIRE DATE: 1/26/03
CHECKED BY: J.W. MOORE DATE: 1/30/03

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
B-3651	3-A

Kimley-Horn and Associates, Inc.
P.O. BOX 33068
RALEIGH, N.C. 27636-3068

NORTH CAROLINA PROFESSIONAL SEAL 024436 ENGINEER JEFFREY W. MOORE 3-26-04

RIGHT OF WAY AREA DATA

PARCEL NO.	PROPERTY OWNERS NAMES	TOTAL ACREAGE	AREA TAKEN	AREA REMAINING RT.	AREA REMAINING LT.	CONST. EASE.	PERM. DRAIN. EASE.	TEMP. DRAIN. EASE.
1	VILLAGES OF MILLSTREAM	2982 SF	736 SF	2246 SF				
	HOMEOWNERS ASSOCIATION, INC.							
2	GUILFORD COUNTY & THE CITY	5.49 AC	0.75 AC	4.74 AC	-0-	0.20 AC		
	OF GREENSBORO & THE PUBLIC							
3	BENJAMIN J. WESTON &	1.51 AC			1.51 AC			276 SF
	RUTH L. WESTON							
4	GUILFORD COUNTY, CITY OF							128 SF
	GREENSBORO, & THE PUBLIC							
5	GUILFORD COUNTY & THE CITY	2.25 AC	0.44 AC	1.81 AC	-0-			
	OF GREENSBORO & THE PUBLIC							
6	VILLAGES OF MILLSTREAM	791 SF	791 SF	-0-	-0-			
	HOMEOWNERS ASSOCIATION, INC.							
7	MANALO WILLIAMS	8841 SF	8841 SF	-0-	-0-			
8	VILLAGES OF MILLSTREAM HOA	10931 SF	7387 SF	3544 SF				
9	D.R. HORTON, INC.	16682 SF			16682 SF	657 SF		
9A	VILLAGES OF MILLSTREAM HOA	5358 SF			5358 SF	226 SF		
10	D.R. HORTON, INC.	10586 SF	1556 SF	9030 SF				
11	LAUREL PARK - PHASE 1A					645 SF		
12	D.R. HORTON, INC.	10111 SF		10111 SF				
13	D.R. HORTON, INC.	19022 SF			19022 SF	472 SF		

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)

| STATION | LOCATION (LT, RT, OR CL) | STRUCTURE NO. FROM | STRUCTURE NO. TO | TOP ELEVATION | INVERT IN ELEVATION | INVERT OUT ELEVATION | CRITICAL SLOPE | CLASS III R.C. PIPE (UNLESS NOTED OTHERWISE) 12" | 15" | 18" | 24" | 30" | 36" | 42" | 48" | BITUMINOUS COATED C.S. PIPE TYPE B (UNLESS NOTED OTHERWISE) 12" (.064) | 15" (.064) | 18" (.064) | 24" (.064) | 30" (.079) | 36" (.079) | 42" (.109) | 48" (.109) | 15" SIDE DRAIN PIPE | 18" SIDE DRAIN PIPE | 24" SIDE DRAIN PIPE | ENDWALLS STD. 838.01 OR STD. 838.11 (UNLESS NOTED OTHERWISE) CU. YDS. R.C.P. | ENDWALLS CU. YDS. C.S.P. | QUANTITIES FOR DRAINAGE STRUCTURES * TOTAL L.F. FOR PAY QUANTITY SHALL BE COL. "A" + (1.3 X COL. "B") LIN. *FT. PER EACH (0' THRU 5.0') | A: 5.0' THRU 10.0' | B: 10.0' AND ABOVE | TYPE OF CONSTRUCTION PERMITTED BRICK | BLOCK | CONCRETE | PRECAST | C.B. STD. 840.01 OR STD. 840.02 | FRAME, GRATES & HOOD STANDARD 840.03 TYPE OF GRATE E | F | G | D.I. STD. 840.14 OR STD. 840.15 | D.I. FRAME & GRATE STD. 840.16 | M.D.I. TYPE "A" STD. 840.17 OR 840.26 | M.D.I. TYPE "B" STD. 840.18 OR 840.27 | M.D.I. TYPE "D" STD. 840.19 OR 840.28 | M.D.I. FRAME WITH GRATE STD. 840.22 | M.D.I. FRAME WITH TWO GRATES STD. 840.22 | M.D.I. (N.S.) FRAME WITH GRATE STD. 840.24 | M.D.I. (N.S.) FRAME WITH TWO GRATES STD. 840.24 | ADJUSTMENT OF CATCH BASINS | CONV. EXIST. C.B. TO J.B. | CONV. EXIST. C.B. TO T.B.J.B. | M.H. FRAME & COVER STD. 840.54 | CORR. STEEL ELBOWS NO. & SIZE | CONC. COLLARS CL. "B" C.Y. STD 840.72 | CONC. & BRICK PIPE PLUG, C.Y. STD. 840.71 | PIPE REMOVAL LIN.FT. | REMARKS |
|---|---|---|---|---|---|---|---|---