

County: Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0003	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0004	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0005	0106000000-E	230	BORROW EXCAVATION	21,300 CY		
0006	0199000000-E	SP	TEMPORARY SHORING	1,300 SF		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	150 TON		
0008	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	772 LF		
0009	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	376 LF		
0010	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	160 LF		
0011	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	76 LF		
0012	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0013	0995000000-E	340	PIPE REMOVAL	824 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	520 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,640 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,550 TON		
0018	1514000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5A	1,350 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	230 TON		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0021	2264000000-E	840	PIPE PLUGS	0.5 CY		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	19 EA		
0023	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	12 LF		
0024	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	2 EA		
0025	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	8 EA		
0026	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	6 EA		
0027	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0028	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0029	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,750 LF		
0030	2591000000-E	848	4" CONCRETE SIDEWALK	950 SY		
0031	2598000000-E	848	CONCRETE WHEELCHAIR RAMPS	14 SY		
0032	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	2 EA		
0033	2830000000-N	858	ADJUSTMENT OF MANHOLES	5 EA		
0034	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	9 EA		
0035	2893000000-N	SP	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0036	3030000000-E	862	STEEL BM GUARDRAIL	975 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0038	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0039	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0040	3628000000-E	876	PLAIN RIP RAP, CLASS I	63 TON		
0041	3649000000-E	876	PLAIN RIP RAP, CLASS B	6 TON		
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	785 SY		
0043	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	27.25 SF		
0044	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	54 LF		
0045	4102000000-N	904	SIGN ERECTION, TYPE E	5 EA		
0046	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	11 EA		
0047	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	444 SF		
0048	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	96 SF		
0049	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	92 SF		
0050	4425000000-N	1125	WARNING FLAG SETS	3 EA		
0051	4430000000-N	1130	DRUMS	40 EA		
0052	4435000000-N	1135	CONES	30 EA		
0053	4446100000-E	SP	BARRICADES (TYPE III)	134 LF		
0054	4455000000-N	1150	FLAGGER	280 MD		
0055	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	3 EA		
0057	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	2 EA		
0058	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,530 LF		
0059	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	240 LF		
0060	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	28,829 LF		
0061	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	133 LF		
0062	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	375 LF		
0063	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	8 EA		
0064	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,100 LF		
0065	5318000000-E	1505	PAVEMENT REPAIR FOR UTILITY WORK	8 TON		
0066	5402000000-E	1510	DI RESTRAINED JOINT WATER PIPE FITTINGS, 250# MIN WP	3,770 LB		
0067	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	2 EA		
0068	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	2 EA		
0069	5804000000-E	1530	FILL OR REMOVE ABANDONED 12" PIPE, ***** (DI WATER)	410 LF		
0070	5822000000-N	1530	BREAK DOWN & REBUILD EXISTING MANHOLE	1 EA		
0071	5888000000-E	SP	GENERIC UTILITY ITEM 12" DI RESTRAINED JOINT WATER PIPE, PC 350	535 LF		
0072	5888000000-E	SP	GENERIC UTILITY ITEM 6" DI RESTRAINED JOINT WATER PIPE, PC 350	81 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI RESTRAINED JOINT WATER PIPE, PC 350	24 LF		
0074	5900000000-E	SP	GENERIC UTILITY ITEM #67 STONE FOR FOUNDATION CONDITIONING	34 TON		
0075	5900000000-E	SP	GENERIC UTILITY ITEM #67 STONE FOR PIPE BEDDING	34 TON		
0076	6000000000-E	1605	TEMPORARY SILT FENCE	675 LF		
0077	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0078	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	305 TON		
0079	6012000000-E	1610	SEDIMENT CONTROL STONE	265 TON		
0080	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0081	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0082	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0083	6024000000-E	1622	TEMPORARY SLOPE DRAINS	55 LF		
0084	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0085	6029000000-E	SP	SAFETY FENCE	585 LF		
0086	6030000000-E	1630	SILT EXCAVATION	585 CY		
0087	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,760 SY		
0088	6042000000-E	1632	1/4" HARDWARE CLOTH	600 LF		
0089	6069000000-E	1638	STILLING BASINS	300 CY		
0090	6084000000-E	1660	SEEDING & MULCHING	4 ACR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6087000000-E	1660	MOWING	1.5 ACR		
0092	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0093	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0094	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0095	6108000000-E	1665	FERTILIZER TOPDRESSING	2.75 TON		
0096	6111000000-E	SP	IMPERVIOUS DIKE	365 LF		
0097	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0098	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0099	6120000000-E	SP	CULVERT DIVERSION CHANNEL	360 CY		

CULVERT ITEMS

0100	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+06.68 -L-)	Lump Sum	L.S.	
0101	8126000000-N	414	CULVERT EXCAVATION, STA ***** (17+06.68 -L-)	Lump Sum	L.S.	
0102	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	327 TON		
0103	8804000000-N	SP	GENERIC CULVERT ITEM CONSTRUCTION OF CULVERT AT STA 17+06.68 -L-	Lump Sum	L.S.	

1255/Dec10/Q83239.75/D416305500000/E103

Total Amount Of Bid For Entire Project :

C201351
Guilford County

2/16/99

Contract No: C201351
County: Guilford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General