

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	6 TON		
0003	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
0004	1220000000-E	545	INCIDENTAL STONE BASE	485 TON		
0005	1243000000-E	SP	SHOULDER CONSTRUCTION	8.77 SMI		
0006	1245000000-E	SP	SHOULDER RECONSTRUCTION	2.92 SMI		
0007	1330000000-E	607	INCIDENTAL MILLING	1,422 SY		
0008	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	8,847 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	15,760 TON		
0010	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,327 TON		
0011	3030000000-E	862	STEEL BM GUARDRAIL	300 LF		
0012	3135000000-N	862	W-TR STEEL BM GUARDRAIL TRANSITION SECTIONS	4 EA		
0013	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	11 EA		
0014	3360000000-E	863	REMOVE EXISTING GUARDRAIL	350 LF		
0015	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	61,752 LF		
0016	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	61,752 LF		
0017	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	202 LF		
0018	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	61,752 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	386	EA	
0020	6000000000-E	1605	TEMPORARY SILT FENCE	650	LF	
0021	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50	TON	
0022	6012000000-E	1610	SEDIMENT CONTROL STONE	20	TON	
0023	6030000000-E	1630	SILT EXCAVATION	450	CY	
0024	6110000000-E	SP	RESIDENTIAL SEEDING	2.36	ACR	

1025/Dec14/Q215601.05/D77017100000/E24

Total Amount Of Bid For Entire Project :

C201354
Guilford County

2/16/99

Contract No: C201354
County: Guilford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General