

5/28/99

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201232

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+41.00)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	1,100	CY	UNDERCUT EXCAVATION
0134000000-E	240	55	CY	DRAINAGE DITCH EXCAVATION
0195000000-E	265	600	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	600	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	14	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0654000000-E	310	132	LF	**** X **** CS PIPE ARCH CUL- VERTS, ***** THICK (72" X 44", 0.139")
0995000000-E	340	199	LF	PIPE REMOVAL
1121000000-E	520	256	TON	AGGREGATE BASE COURSE
1220000000-E	545	50	TON	INCIDENTAL STONE BASE
1275000000-E	600	250	GAL	PRIME COAT
1330000000-E	607	120	SY	INCIDENTAL MILLING
1489000000-E	610	410	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	450	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	47	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2000000000-N	806	11	EA	RIGHT OF WAY MARKERS
2022000000-E	815	70	CY	SUBDRAIN EXCAVATION
2033000000-E	815	52	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	300	LF	6" PERFORATED SUBDRAIN PIPE
2055000000-E	815	9	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS

ItemNumber	Sec #	Quantity	Unit	Description
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
2556000000-E	846	75	LF	SHOULDER BERM GUTTER
3030000000-E	862	325	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3389100000-N	SP	1	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY
3656000000-E	876	225	SY	FILTER FABRIC FOR DRAINAGE
4025000000-E	901	15.5	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
4072000000-E	903	40	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
4102000000-N	904	3	EA	SIGN ERECTION, TYPE E
4155000000-N	907	8	EA	DISPOSAL OF SIGN SYSTEM, U- CHANNEL
4412000000-E	SP	124	SF	WORK ZONE SIGNS (STATIONARY)
4412200000-E	SP	88	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	2	EA	WARNING FLAG SETS
4430000000-N	1130	25	EA	DRUMS
4435000000-N	1135	25	EA	CONES
4446100000-E	SP	144	LF	BARRICADES (TYPE III)
4450000000-N	1150	960	HR	FLAGGER
4460000000-N	1155	2	EA	WARNING LIGHTS (TYPE B)
4650000000-N	1251	50	EA	TEMPORARY RAISED PAVEMENT MARKERS
4685000000-E	1205	2,600	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4686000000-E	1205	2,600	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)

ItemNumber	Sec #	Quantity	Unit	Description
4710000000-E	1205	40	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
4810000000-E	1205	12,400	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	35	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	850	LF	TEMPORARY SILT FENCE
6006000000-E	1610	125	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	350	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	100	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING
6024000000-E	1622	50	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6030000000-E	1630	410	CY	SILT EXCAVATION
6033000000-E	1631	360	SY	SYNTHETIC ROVING
6036000000-E	1631	635	SY	MATTING FOR EROSION CONTROL
6038000000-E	SP	375	SY	PERMANENT SOIL REINFORCEMENT MAT
6084000000-E	1660	1.5	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6123000000-E	1670	0.5	ACR	REFORESTATION

27-JUL-2004 15:30
B:\Proj\B3670\Draw
PDD\Ncd