STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

SHEET NO. B-3670 /-A ROADWAY DESIGN **ENGINEER**

PROJECT REFERENCE NO.

KEM 12/9/03

INDEX OF SHEETS

Sheet Number	Sheet
1 .	Title Sheet
1-A	Index Of Sheets, General Notes and List Of Standards
1-B	Conventional Symbols
2	Pavement Schedule, Typical Sections Details of Undercut, And Details of Wedging
2-A thur 2-B	Detail Of Reinforced Bridge Approach Fills
2-C thur 2-F	Detail Of Guardrail Installation
3	Summary Of Quantities
3-A	Summary of Drainage Summary Of Asphalt Pavement Removal,
	Guardrail Summary And Summary Of Earthwork
3-B	Parcel Index Sheet
4 & 4A	Plan Sheets
5	Profile Sheet
TCP-1 thru TCP-6	Traffic Control Plans
PM-1	Pavement Marking Plans
EC-1 thru EC-6	Erosion Control Plans
RF-1	Reforestation Details
SIGN-1 thru SIGN-2	Signing Plans
UO-1	Utilities By Others
X-1 thru X-12	Cross-Sections
S-1 thru S-17	Structure Plans

GENERAL NOTES:

2002 SPECIFICATIONS EFFECTIVE: 01-15-02

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL

SHOULDER CONSTRUCTION:

SHOULDER CONSTRUCTION ON HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

UNDERDRAINS:

UNDERDRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 815.03 AT LOCATIONS DIRECTED BY THE ENGINEER.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC WILL BE PAID FOR AS "EXTRA WORK" IN ACCORDANCE WITH SECTION 104-7.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE SOUTH RIVER EMC – (POWER) AND SPRINT (TELEPHONE).

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

EFF. 01-15-02

ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch -N. C. Department of Transportation - Raleigh, N. C., Dated January 15, 2002 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.

200.03 Method of Clearing - Method III

225.02 Guide for Grading Subgrade - Secondary and Local

225.04 Method of Obtaining Superelevation - Two Lane Pavement

300.01 Method of Pipe Installation - Method 'A'

560.01 Method of Shoulder Construction - High Side of Superelevated Curve - Method I

806.01 Concrete Right-of-Way Marker

806.02 Granite Right-of-Way Marker

815.03 Pipe Underdrain and Blind Drain

846.01 Concrete Curb, Gutter and Curb & Gutter

862.01 Guardrail Placement

862.03 Structure Anchor Units