

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+41.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	1,100 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	55 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	600 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	600 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	14 TON		
0011	0654000000-E	310	**** X **** CS PIPE ARCH CUL- VERTS, ***** THICK (72" X 44", 0.139")	132 LF		
0012	0995000000-E	340	PIPE REMOVAL	199 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	256 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0015	1275000000-E	600	PRIME COAT	250 GAL		
0016	1330000000-E	607	INCIDENTAL MILLING	120 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	410 TON		
0018	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	450 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	47 TON		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	11 EA		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	70 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	52 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2556000000-E	846	SHOULDER BERM GUTTER	75 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	325 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1 EA		
0033	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	225 SY		
0034	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	15.5 SF		
0035	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	40 LF		
0036	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0037	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8 EA		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	124 SF		
0039	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	88 SF		
0040	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0041	4430000000-N	1130	DRUMS	25 EA		
0042	4435000000-N	1135	CONES	25 EA		
0043	4446100000-E	SP	BARRICADES (TYPE III)	144 LF		
0044	4450000000-N	1150	FLAGGER	960 HR		
0045	4460000000-N	1155	WARNING LIGHTS (TYPE B)	2 EA		
0046	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	50 EA		
0047	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,600 LF		
0048	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,600 LF		
0049	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	40 LF		
0050	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,400 LF		
0051	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	35 EA		
0052	6000000000-E	1605	TEMPORARY SILT FENCE	850 LF		
0053	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	125 TON		
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	350 TON		
0055	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		
0056	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0058	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0059	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0060	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0061	6030000000-E	1630	SILT EXCAVATION	410 CY		
0062	6033000000-E	1631	SYNTHETIC ROVING	360 SY		
0063	6036000000-E	1631	MATTING FOR EROSION CONTROL	635 SY		
0064	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	375 SY		
0065	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0066	6087000000-E	1660	MOWING	1 ACR		
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0068	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0069	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0070	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0071	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0072	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0073	6123000000-E	1670	REFORESTATION	0.5 ACR		

---

**STRUCTURE ITEMS**


---

0074	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+41.00-L-)	Lump Sum	L.S.	
------	--------------	-----	--	----------	------	--

---

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15+41.00-L-)	Lump Sum	L.S.	
0076	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	22.4 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+41.00-L-)	Lump Sum	L.S.	
0078	8217000000-E	425	REINFORCING STEEL (BRIDGE)	3,572 LB		
0079	8364000000-E	450	HP12X53 STEEL PILES	270 LF		
0080	8503000000-E	460	CONCRETE BARRIER RAIL	99.5 LF		
0081	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	220 TON		
0082	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	240 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	497.5 LF		
0820/Dec09/Q32885.4/D354481900000/E84			Total Amount Of Bid For Entire Project :			

C201232 (B-3670)  
Johnston County

2/16/99

Contract No: C201232  
County: Johnston

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General