

PROJECT NO.	SHEET NO.	TOTAL NO.
8CR.10771.3, 8CR.20771.3	6	9
8CR.307716.3, 8CR.307736.3		

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	4685000000-E	4686000000-E	4695000000-E	4725000000-E	4810000000-E		4900000000-N		4905000000-N	
					4" X 90 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	8" X 90 M YELLOW THERMO LF	THERMO LT ARROW 90 M EA	4" YELLOW PAINT LF	4" WHITE PAINT LF	CYAN & RED MARKERS EA	YELLOW & YELLOW MARKERS EA	SNOW PLOWABLE MARKERS EA	
8CR.10771.3	Richmond	1	NC 73	FROM SR 1155 TO MONT. CO. LINE	17,500	14,000							140	
TOTAL FOR PROJ NO. 8CR.10771.3					17,500	14,000							140	
8CR.20771.3	Richmond	2	SR 1966	FROM SR 1108 TO NC 177	32,000	30,000	450	10			20	315		
TOTAL FOR PROJ NO. 8CR.20771.3					32,000	30,000	450	10			20	315		
											335			
8CR.307716.3	Richmond	3	SR 1615	FROM NC 177 TO CONST. JT.						7,500				
TOTAL FOR PROJ NO. 8CR.307716.3										7,500				
										7,500				
8CR.307736.3	Richmond	4	SR 1423	FROM US 1 TO SR 1424						15,200	19,000			
		5	SR 1516	FROM US 1 TO N. LEE ST.						4,200	1,500			
TOTAL FOR PROJ NO. 8CR.307736.3										19,400	20,500			
										39,900				
GRAND TOTAL					49,500	44,000	450	10		26,900	20,500	20	315	140
										47,400		335		