

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

# SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200966

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0022000000-E	225	2,000	CY	UNCLASSIFIED EXCAVATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+59.00)
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0057000000-E	226	50	CY	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0134000000-E	240	15	CY	DRAINAGE DITCH EXCAVATION
0318000000-E	300	6	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0343000000-E	310	32	LF	15" SIDE DRAIN PIPE
0708000000-E	310	24	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0995000000-E	340	41	LF	PIPE REMOVAL
1121000000-E	520	590	TON	AGGREGATE BASE COURSE
1220000000-E	545	100	TON	INCIDENTAL STONE BASE
1275000000-E	600	460	GAL	PRIME COAT
1525000000-E	SP	340	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	23	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	100	LF	SHOULDER BERM GUTTER
3030000000-E	862	75	LF	STEEL BM GUARDRAIL
3045000000-E	862	100	LF	STEEL BM GUARDRAIL, SHOP CURVED
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3195000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III

ItemNumber	Sec #	Quantity	Unit	Description
3270000000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3649000000-E	876	30	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	400	SY	FILTER FABRIC FOR DRAINAGE
4400000000-E	1110	211	SF	WORK ZONE SIGNS (STATIONARY)
4405000000-E	1110	192	SF	WORK ZONE SIGNS (PORTABLE)
4410000000-E	1110	70	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	2	EA	WARNING FLAG SETS
4430000000-N	1130	10	EA	DRUMS
4435000000-N	1135	25	EA	CONES
4445000000-E	1145	96	LF	BARRICADES (TYPE III)
4450000000-N	1150	160	HR	FLAGGER
4465000000-N	1160	1	EA	TEMPORARY CRASH CUSHIONS
4485000000-E	1170	30	LF	PORTABLE CONCRETE BARRIER
4810000000-E	1205	13,600	LF	PAINT PAVEMENT MARKING LINES (4")
6000000000-E	1605	325	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	250	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	150	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6029000000-E	SP	150	LF	SAFETY FENCE
6030000000-E	1630	310	CY	SILT EXCAVATION
6036000000-E	1631	760	SY	MATting FOR EROSION CONTROL
6042000000-E	1632	25	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	4	EA	SPECIAL STILLING BASINS

ItemNumber	Sec #	Quantity	Unit	Description
6084000000-E	1660	1.5	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1.25	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6123000000-E	1670	0.1	ACR	REFORESTATION

5/28/99

01-OCT-2004 13:10  
RD203029 Friday October 01 2004 sum3 ELOrtega rd-09oce34